

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS / LIST OF STANDARDS / GENERAL NOTES
3	SUMMARY OF QUANTITIES
4-8	LOCATION MAPS
9-19	SCOUR REPAIR PLAN SHEETS

LIST OF STANDARDS

000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
701001-01	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY
701006-02	OFF-ROAD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701011-01	OFF-ROAD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701201-02	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS > 45 MPH
701901	TRAFFIC CONTROL DEVICES
701101-01	<i>OFF ROAD OPERATIONS, MULTILANE, 15' TO 24' FROM PAVT. EDGE</i>
701106-01	<i>OFF ROAD OPERATIONS, MULTILANE, 15' AWAY</i>

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THE WORK INCLUDED IN THIS PROJECT CONSISTS OF SCOUR REPAIR, CHANNEL EXCAVATION AND ANY OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING STRUCTURE HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO THE CONSTRUCTION OR ORDERING OF MATERIAL. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION OR A CHANGE IN THE SCOPE OF THE WORK. THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

THE ACTUAL LOCATIONS OF THE SCOUR REPAIR SHALL BE DETERMINED BY THE ENGINEER IN THE FIELD.

THE LOCATIONS AND/OR DEPTHS OF UNDERGROUND UTILITIES SHOWN HAVE BEEN TAKEN FROM INFORMATION FURNISHED BY THE UTILITY OWNERS AND MUST BE CONSIDERED APPROXIMATE. FIELD MARKING OF FACILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE THROUGH THE J.U.L.I.E. SYSTEM BY CALLING 800.892.0123

ACCESS TO THE VARIOUS WORK LOCATIONS ARE ON RIGHT-OF-WAY, EXCEPT AS NOTED:

- LOCATION 1: S.N. 015-0036, N.W. QUADRANT
- LOCATION 3: S.N. 018-2005, WEST SIDE OF STRUCTURE
- LOCATION 6: S.N. 012-2009, SOUTH END OF STRUCTURE
- LOCATION 7: S.N. 012-8801, N.E. QUADRANT

FILE NAME = c:\projects\74348\d774348-shr-index.dgn	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STANDARDS & GENERAL NOTES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE = 50,000' / IN.	PLOT DATE = 9/9/2008	DRAWN -	REVISED -		SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	VARIOUS	19	2
		CHECKED -	REVISED -				D7 SCOUR REPAIR 2009-1	ILLINOIS	CONTRACT NO. 74348		
		DATE -	REVISED -				FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

• VARIOUS ROUTES *Rev.*