



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 30, 2008

SUBJECT: FAP Route 609 (IL RT 163)
Project TASK 09-24-01
Section 76RS-3, 76-2BR-2I
St. Clair County
Contract No. 76A34
Item No. 22, November 7, 2008 Letting
Addendum C

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page ii of the Table of Contents to the Special Provisions.
2. Revised pages 59 - 65 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm
Interim Bureau Chief
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 8; Mike Renner; R. E. Anderson;
Estimates

TBW:DB:jc

ENGINEER’S FIELD OFFICE TYPE A (BDE) 34

EQUIPMENT RENTAL RATES (BDE)..... 37

HOT-MIX ASPHALT - FIELD VOIDS IN THE MINERAL AGGREGATE (BDE) 38

HOT-MIX ASPHALT – PLANT TEST FREQUENCY (BDE) 39

HOT-MIX ASPHALT – TRANSPORTATION (BDE) 40

IMPACT ATTENUATORS, TEMPORARY (BDE) 41

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) 43

PAYMENTS TO SUBCONTRACTORS (BDE) 43

PERSONAL PROTECTIVE EQUIPMENT (BDE) 44

PLASTIC BLOCKOUTS FOR GUARDRAIL (BDE) 44

PORTLAND CEMENT CONCRETE PLANTS (BDE) 45

PRECAST CONCRETE HANDLING HOLES (BDE) 46

RECLAIMED ASPHALT PAVEMENT (RAP) (BDE) 47

REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) 53

REINFORCEMENT BARS (BDE) 54

REINFORCEMENT BARS - STORAGE AND PROTECTION (BDE)..... 55

SEEDING (BDE) 55

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... 56

SILT FILTER FENCE (BDE) 58

STEEL PLATE BEAM GUARDRAIL (BDE) 58

STONE GRADATION TESTING (BDE)..... 58

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 58

TEMPORARY EROSION CONTROL (BDE) 65

THERMOPLASTIC PAVEMENT MARKINGS (BDE) 66

TRAINING SPECIAL PROVISIONS 67

WATER BLASTER WITH VACUUM RECOVERY (BDE)..... 69

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)..... 69

STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 72

404 PERMIT 76

NATIONWIDE PERMITS AND CONDITIONS 80

IEPA REGIONAL CONDITIONS..... 93

SPECIAL DESIGN PRECAST CONCRETE BOX CULVERTS..... 111

Revised 10/30/2008

This mobilization payment shall be made at least 14 days prior to the subcontractor starting work. The amount paid shall be equal to 3 percent of the amount of the subcontract reported on form BC 260A submitted for the approval of the subcontractor's work.

This provision shall be incorporated directly or by reference into each subcontract approved by the Department.

Revised 10/30/2008

Revised 10/30/2008

Revised 10/30/2008

Revised 10/30/2008

Revised 10/30/2008

Revised 10/30/2008

TEMPORARY EROSION CONTROL (BDE)

Effective: November 1, 2002

Revised: January 1, 2008

Revise the third paragraph of Article 280.03 of the Standard Specifications to read:

“Erosion control systems shall be installed prior to beginning any activities which will potentially create erodible conditions. Erosion control systems for areas outside the limits of construction such as storage sites, plant sites, waste sites, haul roads, and Contractor furnished borrow sites shall be installed prior to beginning soil disturbing activities at each area. These offsite systems shall be designed by the Contractor and be subject to the approval of the Engineer.”

Add the following paragraph after the third paragraph of Article 280.03 of the Standard Specifications:

“The temporary erosion and sediment control systems shown on the plans represent the minimum systems anticipated for the project. Conditions created by the Contractor’s operations, or for the Contractor’s convenience, which are not covered by the plans, shall be protected as directed by the Engineer at no additional cost to the Department. Revisions or modifications of the erosion and sediment control systems shall have the Engineer’s written approval.”

Add the following paragraph after the ninth paragraph of Article 280.07 of the Standard Specifications:

“Temporary or permanent erosion control systems required for areas outside the limits of construction will not be measured for payment.”

Revised 10/30/2008