

SUMMARY OF QUANTITIES

F.A.D. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
609	*	ST. CLAIR	350	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 76RS-2, 76-2BR-21				

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000	1000	SFTY 2A SCOUR MIT
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	254	254		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	579	579		
20100500	TREE REMOVAL, ACRES	ACRE	2.3	2.3		
20200100	EARTH EXCAVATION	CU YD	45923	45923		
20300100	CHANNEL EXCAVATION	CU YD	1012		1012	
20800150	TRENCH BACKFILL	CU YD	952	952		
25000100	SEEDING, CLASS 1	ACRE	0.7	0.7		
25000200	SEEDING, CLASS 2	ACRE	14.1	14.1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1350	1350		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1350	1350		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1350	1350		
25000700	AGRICULTURAL GROUND LIMESTONE	TON	30	30		
25100115	MULCH, METHOD 2	ACRE	14.8	14.8		
25100630	EROSION CONTROL BLANKET	SO YD	8093	8093		
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SO YD	493	493		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4450	4450		
28000300	TEMPORARY DITCH CHECKS	EACH	81	81		
28000400	PERIMETER EROSION BARRIER	FOOT	1088	1088		
28000500	INLET AND PIPE PROTECTION	EACH	49	49		
28100107	STONE RIPRAP, CLASS A4	SO YD	779	779		
28100109	STONE RIPRAP, CLASS A5	SO YD	753		753	
28200200	FILTER FABRIC	SO YD	1532	779	753	
31000600	PROCESSING LIME STABILIZED SOIL MIXTURE 12"	SO YD	4158	4158		
30201500	LIME	TON	96	96		
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	155	155		
31200100	STABILIZED SUB-BASE 4"	SO YD	1856	1856		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	348	348		
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SO YD	955	955		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1001	1001		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	442	442		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11.8	11.8		
40600300	AGGREGATE (PRIME COAT)	TON	75	75		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10		

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000	1000	SFTY 2A SCOUR MIT
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2390	2390		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	160	160		
40600990	TEMPORARY RAMP	SO YD	165	165		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	4860	4860		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	3780	3780		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.9	1.9		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	185	185		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	143	143		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	335	335		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	10124		10124	
42400610	TEMPORARY SIDEWALK	SO FT	1000		1000	
42400800	DETECTABLE WARNINGS	SO FT	360		360	
44000100	PAVEMENT REMOVAL	SO YD	9790	9790		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	4202	4202		
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	668	668		
44000300	CURB REMOVAL	FOOT	640	640		
44000400	GUTTER REMOVAL	FOOT	1771	1771		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	24	24		
44000600	SIDEWALK REMOVAL	SO FT	5603		5603	
44004250	PAVED SHOULDER REMOVAL	SO YD	3723	3723		
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	173	173		
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SO YD	41	41		
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SO YD	50	50		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2550	2550		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2134	2134		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	9811	9811		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1		
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1		
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1		
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1	1		