

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
609		ST. CLAIR	350	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* 76RS-2, 76-2BR-21				

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000	1000	SFTY 2A
			SCOUR MIT			
60255500	MANHOLES TO BE ADJUSTED	EACH	4	4		
60403400	GRATES, TYPE A	EACH	4	4		
60500040	REMOVING MANHOLES	EACH	1	1		
60500050	REMOVING CATCH BASINS	EACH	3	3		
60500060	REMOVING INLETS	EACH	1	1		
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	47.8	47.8		
60602500	CONCRETE GUTTER, TYPE A	FOOT	2955	2955		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3254	3254		
61100605	MISCELLANEOUS CONCRETE	CU YD	10	10		
61101007	STORM SEWERS PROTECTED, CLASS A, 6"	FOOT	200	200		
61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	200	200		
61101011	STORM SEWERS PROTECTED, CLASS A, 10"	FOOT	200	200		
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	8	8		
61139900	STORM SEWERS, SPECIAL 6"	FOOT	200	200		
61140000	STORM SEWERS, SPECIAL 8"	FOOT	200	200		
61140100	STORM SEWERS, SPECIAL 10"	FOOT	200	200		
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	350	350		
*63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	4	4		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	104	104		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	16	16		
66700705	FURNISHING AND ERECTING DRAINAGE MARKERS	EACH	9	9		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		
67100100	MOBILIZATION	L SUM	1	1		
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	150	150		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3187	3187		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	45,725	45,725		

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000	1000	SFTY 2A
			SCOUR MIT			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	318	318		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	230	230		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	603	603		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	850	850		
*78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	36,420	36,420		
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	318	318		
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	208	208		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	157	157		
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	0	0		
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300100	PAVEMENT MARKING REMOVAL	SO FT	544	544		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	157	157		
25100900	TURF REINFORCEMENT MAT	SO YD	4287	4287		
X0323265	REMOVE EXISTING RIPRAP	SO YD	452	390		62
X0325445	RIGHT-OF-WAY AND PROPERTY CORNERS	EACH	37	37		
X0355800	STORM SEWER WATER MAIN 24"	FOOT	105	105		
X0930450	STORM SEWER, WATER MAIN, 15"	FOOT	532	532		
X0930500	STORM SEWER WATER MAIN 18"	FOOT	130	130		
X0326182	TURF REINFORCEMENT MAT NO. 2	SO YD	270	270		
X0326183	TURF REINFORCEMENT MAT NO. 3	SO YD	63	63		
X0326184	REINFORCED CONCRETE PIPE TEE, ELLIPTICAL, EQUIVALENT ROUND-SIZE 48" PIPE WITH 12" RISER	EACH	1	1		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0022800	FENCE REMOVAL	FOOT	160	160		
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2	2		
Z0064505	SECTION CORNER MARKERS	EACH	6	6		
*Z0076600	TRAINEES	Hour	1500	1500		

PLOT DATE = 8/15/2008
 FILE NAME = c:\projects\ed\8955\plan\8955.dgn
 PLOT SCALE = 60:1
 REFERENCE = BRP

© 4080
 *Specialty Items

Rev.