F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
609	•••	ST. CLAIR	350	61
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

•••76RS-3, 76-2BR-2I

DESIGN

	REASON

PLOTS & CHECKS

NO.	REASON

CHECKS

	REASON

EROSION CONTROL SCHEDULE

LOCATION	EROSION CONTROL BLANKET	HEAVY DUTY EROSION CONTROL BLANKET	TURF REINFORCEMENT MAT	TURF REINFORCEMENT MAT NO. 2	TURF REINFORCEMENT MAT NO. 3	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	STONE RIPRAP, CLASS A4	STONE RIPRAP, CLASS A5	FILTER FABRIC
	SQ FT	SQ FT	SQ FT	SQ FT	SQ FT	POUND	EACH	FOOT	EACH	SQ FT	SQ YD	SQ FT
STA. 109+00 RT. TO STA. 110+43 RT.			1194									
STA. 110+00 RT. TO 113+80 RT.								383				
STA. 110+54.50, 31.38' LT.									1			
STA. 110+61.50, 31.38' LT.									1			
STA. 110+73 LT. TO STA. 111+00 LT.			228									
STA. 110+73 RT. TO STA. 113+66 RT	2400											
STA. 110+70, LT.										600		600
STA. 110+70, RT.										740		740
STA. 111+00 LT. TO STA. 116+00 LT.	4000											
STA. 111+50, 30.50' LT.							1					
STA. 114+09, 27' RT.									1			
STA. 114+10 RT. TO STA. 116+00 RT.	1520											
STA. 115+00, 27.00' LT.							1					
STA. 115+50, 27.00' RT.							1					
STA. 116+00 RT. TO STA. 119+45 RT.	2840											
STA. 116+00, 27.00' LT.							1					
STA. 116+50, 28.00' RT.							1					
STA. 117+00, 27.00' LT.							1					
STA. 117+50, 30.00' RT.							1					
STA. 118+00, 27.00' LT.							1					
STA. 118+50, 31.50' RT.							1					
STA. 119+00, 30.50' LT.							1					
STA. 119+90, 76' RT.									1			
STA. 120+05 TO STA. 136+00						450						
STA. 120+19, 32' RT.									1			
STA. 120+50, 32' LT.									1			
STA. 123+49, 27' LT.									1			
STA. 124+00, 29.00' RT.							1					
STA. 130+00 RT. TO STA. 131+00 RT.	2367											
STA. 130+50 LT. TO STA. 131+00 LT.	1227											
STA. 131+00 RT. TO STA. 133+20 RT.	5944											
STA. 134+00 LT. TO STA. 135+60 LT.			978									
ZINGG ROAD												
STA. 496+00, 22.50' LT.							1					
STA. 2+38, 18.00' RT. (STAGE 1)									1			
STA. 498+62, 18.00' LT.							1					
STA. 498+62, 16.00' RT.							1					
MINE HAUL ROAD												
STA. 500+75, 58.50' RT. (STAGE 1)							1					
STA. 500+75, 21.00' RT.							1					
STA. 502+25, 19.00' RT. (STAGE 1)							1					
STA. 502+25, 21.00' LT.							1					
STA. 502+25, 57.00' RT. (STAGE 1)							1					
STA. 502+25, 21.00' RT.							1					
STA. 2+00, 18.00' LT. (STAGE 1)									1			
LAKE LANE (EAST)												
STA. 601+75, 12.00' LT.							1					
STA. 601+75, 12.00' RT.							1					
SCOUR MITIGATION											753	6777
TOTAL	72838	4435	38584	2428	568	4428	81	1088	49	7010	753	13787
	USE 8093 SQ Y	USE 493 SQ YD	USE 4287 SQ YD	USE 270 SQ YD	USE 63 SQ YD	USE 4450				USE 779 SQ YD	USE 753	USE 1532 SQ YD

SEEDING SCHEDULE

LOCATION	SEEDING, CLASS 1	SEEDING, CLASS 2	AGRICULTURAL GROUND LIMESTONE (2 TON / ACRE)	NITROGEN FERTILIZER NUTRIENT (90 LBS / ACRE)	PHOSPHORUS FERTILIZER NUTRIENT (90 LBS / ACRE)	POTASSIUM FERTILIZER NUTRIENT (90 LBS / ACRE)	MULCH, METHOD 2
	ACRE	ACRE	TON	POUND	POUND	POUND	ACRE
IL 163							
STA. 10+00, RT. TO STA. 23+70.51, RT.	0.4		0.8	36	36	36	0.40
STA. 23+70.51, RT. TO STA. 93+60.00, RT.		4.97	10.0	448	448	448	4.97
STA. 93+60.00, RT. TO STA. 120+05.00, RT.		1.28	2.6	116	116	116	1.28
STA. 120+05.00, RT. TO STA. 136+00.00, RT.		0.89	1.8	81	81	81	0.89
STA. 10+00, LT. TO STA. 22+89.00, LT.	0.3		0.6	27	27	27	0.30
STA. 22+89.00, LT. TO STA. 93+60.00, LT.		4.35	8.7	392	392	392	4.35
STA. 93+60.00, LT. TO STA. 120+05.00, LT.		1.96	4.0	177	177	177	1.96
STA. 120+05.00, LT. TO STA. 136+00.00, LT.		0.61	1.3	55	55	55	0.61
TOTAL	0.7	14.06	29.8	1332	1332	1332	14.76
		USE 14.1	USE 30.0	USE 1350	USE 1350	USE 1350	USE 14.8

REVISIONS	
NAME	DATE
IDOT REVIEW	MAR/OB

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM WATER POLLUTION PREVENTION PLAN

FAP ROUTE 609 (IL RTE 163)
SECTION 76RS-3, 76-2BR-2I
ST. CLAIR COUNTY

SCALE: VERT. HORIZ.
DATE: 11/25/02
DRAWN BY: VERENSKI
DESIGNED BY: BOTT
CHECKED BY: EMRICK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
3066 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
T 217 ? 793-8844

COMPUTER FILE NO. $FILES$
PROJECT: 02076
12/21/07 - MDS

IDOTPL50 1"=50' 8/24/98