

SUMMARY OF QUANTITIES

MCHD

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE SFTY-2A URBAN		
X0326191	BEAM HEAT STRAIGHTENING	L SUM	1	1		
50501130	STRUCTURAL STEEL REPAIR	POUND	1570	1570		
67100100	MOBILIZATION	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1		
X7010600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406, SPECIAL	L SUM	1	1		

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, COMMITMENTS & SUMMARY OF QUANTITIES
- 3-4 TRAFFIC CONTROL DETAILS
- 5-7 BRIDGE REPAIR PLANS

HIGHWAY STANDARDS

- 000001-05
- 701400-02
- 701406-04
- 701601-05
- 701901

GENERAL NOTES:

1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMEREN IP
 - AMEREN UE
 - AT&T ILLINOIS
 - CITY OF EAST ST. LOUIS - SEWER
 - ILLINOIS AMERICAN WATER
 - PAETEC/MCLEOD USA TELECOMMUNICATIONS, INC.
 - METRO
 MEMBERS OF J.U.L.I.E. (800) 892-0123 OR 811 ARE INDICATED BY *. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
4. A CHANGEABLE MESSAGE SIGN SHALL BE REQUIRED ON THIS PROJECT. THE MESSAGE SIGN SHALL BE PLACED TWO WEEKS BEFORE ANY LANE RESTRICTIONS. THE MESSAGE SIGN SHALL BE PLACED ALONG EASTBOUND I-64 BEFORE THE TRI-LEVEL.
5. NO OVERNIGHT CLOSURES WILL BE PERMITTED ON THIS PROJECT.
6. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE BEGINNING OF THE PROJECT AND ON EASTBOUND I-64 AND SOUTHBOUND I-55/I-70 BEFORE THE TRI-LEVEL AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE.
7. THERE IS AN INLET LOCATED ON THE RIGHT SHOULDER OF EASTBOUND I-64 NEAR THE STRUCTURE. THIS INLET WILL BE COVERED WITH A STEEL PLATE FOR THE DURATION OF THIS PROJECT. THE PLACEMENT AND REMOVAL OF THIS STEEL PLATE WILL BE PAID FOR ACCORDING TO ART. 109.04.

COMMITMENTS

NONE

FILE NAME =	USER NAME = owenbj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, COMMITMENTS & SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
g:\projects\1676c25\design\1676c25-sh-	lan.dgr	DRAWN -	REVISED -			64	82-IHB-HDF	ST. CLAIR	7	2
	PLOT SCALE = 50,0000 / 1 IN.	CHECKED -	REVISED -							
	PLOT DATE = 8/12/2008	DATE	REVISED							
						SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	
						CONTRACT NO. 76C25				