

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
932	(8,9,11W,RS-1	*	401	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* JOHNSON & POPE				

### SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	JOHNSON COUNTY	POPE COUNTY
				RURAL 80% FEDERAL 20% STATE	RURAL 80% FEDERAL 20% STATE
CONSTRUCTION TYPE CODE				1000	1000
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	781	619	162
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,214	1,075	139
20100500	TREE REMOVAL, ACRES	ACRE	30	27	3
20200100	EARTH EXCAVATION	CU YD	154,702	126,119	28,583
* 20200200	ROCK EXCAVATION	CU YD	14,903	14,277	626
20400100	BORROW EXCAVATION	CU YD	62,452	37,576	24,876
20900110	POROUS GRANULAR BACKFILL	CU YD	868	686	182
25000200	SEEDING, CLASS 2	ACRE	69.55	55.85	13.70
25000305	SEEDING, CLASS 3A	ACRE	17.01	12.15	4.86
25000350	SEEDING, CLASS 7	ACRE	89.55	70.98	18.57
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	14,331	11,360	2,971
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10,748	8,520	2,228
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10,748	8,520	2,228
25000700	AGRICULTURAL GROUND LIMESTONE	TON	173.0	135.9	37.1
25002024	SEEDING, CLASS 4B (MODIFIED)	ACRE	3.0	3.0	0.0
25100115	MULCH, METHOD 2	ACRE	176.12	138.99	37.13
25100630	EROSION CONTROL BLANKET	SQ YD	42,837	33,877	8,960
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	17,912	14,199	3,713
28000300	TEMPORARY DITCH CHECKS	EACH	1,485	1,173	312
28000400	PERIMETER EROSION BARRIER	FOOT	49,194	40,707	8,487
28000500	INLET AND PIPE PROTECTION	EACH	159	129	30
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	4,104	2,945	1,159
28200200	FILTER FABRIC	SQ YD	4,104	2,945	1,159
35100100	AGGREGATE BASE COURSE, TYPE A	TON	1,529	913	616
35650400	BASE COURSE WIDENING 9"	SQ YD	49,878	40,276	9,602
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	1,928	1,747	181
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	804	444	360
40600990	TEMPORARY RAMP	SQ YD	376	186	190
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	31,450	25,657	5,793
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	14,893	12,010	2,883
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	24,290	19,390	4,900

\*specialty items

PLOT DATE = 8/28/2008  
 FILE NAME = 98542.dwg  
 USER NAME = rollaw