

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
932	(8,9,11)W,RS-1	*	401	30
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* JOHNSON & POPE				

### BOX CULVERTS

LOCATION STATION	CONCRETE BOX CULVERT	CLASS SI CONCRETE (MISC)	REINFORCEMENT BARS	EXPANSION BOLTS 3/4 INCH	2" X 8" X 48" PRESSURE TREATED LUMBER	PRECAST CONCRETE BOX CULVERT 7' X 4'	REMOVE & RELAY BOX CULVERT END SECTION CULVERT NO. 1
	CU YD	CU YD	POUND	EACH	EACH	FOOT	EACH
JOHNSON CO.							
98+78.80 LT						8	1
98+78.80 RT						10	1
193+08.45	19.8		3270	40			
245+00.00		6.7	280		2		
305+61.10	29.6		6160	36			
314+02.38	39.6		6460	48			
337+95.30	32.6		6170	36			
344+52.79	15.4		2040	24			
355+78.99	18.4		3340	36			
465+77.62	31		4770	24			
478+62.55	14.4		1890	20			
485+94.17	11.7		1270	16			
SUBTOTAL (JOHNSON CO.)	212.5	6.7	35650	280	2	18	2
POPE CO.							
544+89.51	13.1		1930	40			
575+56.60	40.3		9300	24			
615+34.31	18.9		2270	32			
631+65.86	12.3		1360	28			
652+31.20	16.1		2080	32			
657+67.24	7.3		1000	20			
SUBTOTAL (POPE CO.)	108.0	0.0	17940	176	0	0	0
TOTAL	320.5	6.7	53590	456	2	18	2

### DITCH CHECK REMOVAL SCHEDULE

LOCATION STATION	OFFSET		DITCH CHECK REMOVAL	
			EACH	
JOHNSON CO.				
3+36.47	33.03	RT	1	
3+83.46	26.06	RT	1	
4+14.12	23.25	RT	1	
4+86.55	18.11	RT	1	
5+20.72	17.69	RT	1	
7+11.62	19.44	RT	1	
12+05.71	20.31	RT	1	
12+61.04	19.09	RT	1	
30+17.57	20.66	RT	1	
30+55.41	21.45	LT	1	
81+61.37	22.69	LT	1	
81+82.86	19.35	RT	1	
82+37.38	26.21	LT	1	
105+70.82	18.02	LT	1	
106+32.27	18.49	LT	1	
106+94.45	19.01	LT	1	
107+61.22	18.71	LT	1	
108+47.60	20.44	LT	1	
108+86.49	20.16	LT	1	
109+28.41	20.13	LT	1	
111+77.03	20.66	LT	1	
112+56.21	19.16	LT	1	
114+79.30	21.31	LT	1	
172+44.69	22.95	RT	1	
173+04.93	23.62	RT	1	
173+46.51	23.71	RT	1	
220+31.88	23.92	LT	1	
220+73.18	35.13	LT	1	
236+67.72	21.51	LT	1	
237+23.76	28.36	LT	1	
237+69.43	40.77	LT	1	
237+94.37	41.62	LT	1	
238+57.41	41.97	LT	1	
238+79.99	42.38	LT	1	
296+66.57	20.26	LT	1	
296+79.19	22.96	RT	1	
299+65.81	18.24	LT	1	
301+62.64	25.03	LT	1	
301+66.74	22.89	RT	1	
302+12.11	26.78	LT	1	
302+17.61	23.71	RT	1	
302+61.54	28.63	LT	1	
302+67.85	24.23	RT	1	
303+19.14	25.21	RT	1	
303+70.27	26.2	RT	1	
304+23.57	26.51	RT	1	
304+73.44	27.1	RT	1	
312+59.80	28.07	LT	1	
358+20.73	19.81	RT	1	
359+56.82	26.49	LT	1	
362+06.23	26.82	LT	1	
364+57.13	19.28	RT	1	
365+80.61	20.36	RT	1	
367+11.78	20.06	RT	1	
CONTINUED				

LOCATION STATION	OFFSET		DITCH CHECK REMOVAL	
			EACH	
368+08.13	21.1	RT	1	
431+18.36	26.32	LT	1	
431+50.71	26.11	LT	1	
431+84.74	24.01	LT	1	
432+34.18	20.52	LT	1	
432+72.38	18.81	LT	1	
452+13.54	19.91	LT	1	
454+08.05	25.15	LT	1	
455+08.96	27.75	LT	1	
456+08.98	29.15	LT	1	
456+58.52	29.27	LT	1	
471+99.95	20.93	RT	1	
472+09.58	30.65	LT	1	
472+49.77	21.12	RT	1	
472+74.68	21.43	RT	1	
476+80.64	21.12	LT	1	
477+32.43	22.14	LT	1	
477+80.08	25.75	LT	1	
489+70.52	22.1	RT	1	
489+96.44	21.1	RT	1	
490+25.59	19.15	RT	1	
SUBTOTAL (JOHNSON CO.)			75	
POPE CO.				
598+19.97	40.63	LT	1	
598+47.31	32.00	LT	1	
598+73.46	24.91	LT	1	
599+00.61	20.81	LT	1	
612+35.09	18.57	LT	1	
612+36.84	18.63	RT	1	
613+00.03	18.92	LT	1	
613+03.49	17.89	RT	1	
613+31.75	19.40	LT	1	
613+62.77	18.82	RT	1	
613+65.69	20.19	LT	1	
614+05.74	23.21	LT	1	
614+09.09	19.20	RT	1	
614+24.66	27.47	LT	1	
614+54.43	20.40	RT	1	
628+35.27	19.74	RT	1	
630+11.80	22.94	RT	1	
630+73.03	29.88	RT	1	
631+99.60	31.86	RT	1	
645+01.37	23.47	RT	1	
667+98.55	31.42	LT	1	
668+25.48	32.50	LT	1	
668+73.41	36.00	LT	1	
669+04.77	39.92	LT	1	
669+16.44	32.74	RT	1	
669+31.29	44.36	LT	1	
669+61.16	48.96	LT	1	
669+84.49	52.74	LT	1	
669+98.84	50.22	RT	1	
669+99.69	54.53	LT	1	
SUBTOTAL (POPE CO.)			30	
TOTAL			105	