CONTRACT NO. 98542

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
932	(8,9,11)W,RS-1	*	401	73
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* JOHNSON & POPE

N

50' 0 25' 50'

STA 440+24.25
PIPE CULVERT REMOVAL
EXTEND EXISTING PIPE CULVERT (24" RCP)
PIPE CULVERT
CLASS A, TYPE 1, 24"
10° SKEW RT AHEAD
CONCRETE COLLARS
PRECAST FES 24"
USFL 450.58
DSFL 447.49

ABANDON
EXISTING 24" RCP

STA 445+58.63
EXTEND EXISTING PIPE CULVERT (42" RCP)
PIPE CULVERT
CLASS A, TYPE 1, 42"
9° SKEW RT AHEAD
CONCRETE COLLARS
PRECAST FES 42"
USFL 452.37
DSFL 450.63

PIPE CULVERT REMOVAL

PIPE CULVERT REMOVAL
PIPE CULVERT
CLASS A, TYPE 1, 24"
END SECTIONS, 24"
USFL 455.30
DSFL 454.86

BUILDING
REMOVAL NO. 14

STA. 444+69.10 ℄ FAS 932 =
STA. 10+00.00 ℄ FLATTWOOD ROAD

53°59'25"

TREE REMOVAL, ACRES
TREE REMOVAL, UNIT
EXISTING CONCRETE/BRICK DITCH CHECK TO BE REMOVED
STONE DUMPED RIP RAP, CLASS A4
CLASS D PATCHING

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
NOTE BOOK
NO.
CADD FILE NAME
BY
DATE

PROFILE
SURVEYED
PLOTTED
ALIGNMENT CHECKED
BENCHMARKS
NOTE BOOK
NO.
STRUCTURE NO'S/PIN'S CP'KD
BY
DATE

BM38 - R.R. SPIKE IN P.P. 37.7' LT
ELEV 454.89 STA 438+77.80

+00.00 451.40 | -0.63% | PR RT DITCH | +30.86 450.58 | +5.55% | +00.00 454.42 | +0.95% | +00.00 456.33

+65.48 452.37 | +7.41% | +00.00 454.95 | PR RT DITCH

+16.88 447.49 | +9.28% | +00.00 454.37 | +0.72% | +00.00 455.81 | PR LT DITCH

+52.69 450.63 | +3.97% | +00.00 456.48 | PR LT DITCH

NOTE:
LEFT DITCH PLOTTED 10' BELOW PROFILE DATUM FOR CLARITY

436+00	437+00	438+00	439+00	440+00	441+00	442+00	443+00	444+00	445+00	446+00	447+00	448+00	449+00	450+00	451+00
442.31 / 442.72	444.72 / 444.96	446.89 / 447.20	448.71 / 448.89	450.26 / 450.57	451.69 / 451.97	453.04 / 453.36	454.23 / 454.54	455.38 / 455.71	456.50 / 456.74	457.46 / 457.77	458.19 / 458.38	458.67 / 458.98	458.87 / 459.11	458.89 / 459.23	458.70 / 458.92	458.26 / 458.62	458.00 / 458.26	457.58 / 457.90	457.50 / 457.90	457.59 / 457.90	458.42 / 458.94	459.66 / 459.97	461.27 / 461.62	462.96 / 463.27	464.57 / 464.90	466.21 / 466.52	467.72 / 467.92	468.99 / 469.31	470.11 / 470.45	471.28 / 471.59

•DATE-TIME•
•DGN-FILE•
•CELL-LIB•
•REF-prop30
•REF
•REF

PLAN PROFILE SHEET STA 436+00 TO 451+00