

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX AND HIGHWAY STANDARDS
3-4	SUMMARY OF QUANTITIES
5	SCHEDULE OF QUANTITIES
6-8	LOCATION MAPS
9	ROADWAY PLAN - LOCATION 19
10-17	ALUMINUM SPAN SIGN TRUSS PLANS
18-25	ALUMINUM CANTILEVER SIGN TRUSS PLANS
26-28	BRIDGE MOUNTED SIGN STRUCTURE PLANS
29-30	MONOTUBE SIGN STRUCTURE PLANS
31-33	MISCELLANEOUS SIGN STRUCTURE REPAIR PLANS
34-37	BORING LOGS
38-46	SIGN PANEL PLANS
47	DETAILS FOR DEPRESSED CURB & GUTTER AND SHOULDER TREATMENT AT T&T TY I SPL (BD 34)
48	ENTRANCE AND EXIT RAMP CLOSURE DETAILS (TC 8)
49	SINGLE LANE WEAVE AND MULTI-LANE WEAVE (TC 9)
50	SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC 17)
51	FREEWAY/EXPRESSWAY SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS ON FREEWAYS/EXPRESSWAYS (TC 18)
52	ARTERIAL ROAD INFORMATION SIGNING (TC 22)
53	CENTER LANE CLOSURE, AND SHOULDER LANE (TC 25)

HIGHWAY STANDARDS

STD. NO.	TITLE
606001-05	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
631031-11	TRAFFIC BARRIER TERMINAL, TYPE 6
701101-03	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701400-06	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-07	LANE CLOSURE, FREEWAY/EXPRESSWAY
701402-09	LANE CLOSURE, FREEWAY/EXPRESSWAY, WITH BARRIER
701406-07	LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
701411-08	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS • 45 MPH
701416-07	LANE CLOSURE, FREEWAY/EXPRESSWAY, WITH CROSSOVER AND BARRIER
701421-05	LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS • 45 MPH TO 55 MPH
701426-05	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION, FOR SPEEDS • 45 MPH
701446-04	TWO LANE CLOSURE, FREEWAY/EXPRESSWAY
701901-02	TRAFFIC CONTROL DEVICES
720001-01	SIGN PANEL MOUNTING DETAILS
720021-02	SIGN PANELS, EXTRUDED ALUMINUM TYPE

GENERAL NOTES

1. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
2. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.
3. THE CONTRACTOR SHALL CONTACT THE EXPRESSWAY TRAFFIC OPERATIONS ENGINEER (847-705-4151) SEVENTY-TWO (72) HOURS IN ADVANCE OF ALL LANE, RAMP AND SHOULDER CLOSURES.
4. IT SHALL BE THE CONTACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
5. WHEN ARTIFICIAL LIGHTING IS USED IN NIGHT OPERATIONS THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.
6. FOR OVERHEAD SIGN STRUCTURES, THE END SUPPORTS ARE INCLUDED IN THE COST OF THE OVERHEAD SPAN OR CANTILEVER STRUCTURE.
7. RESTORATION OF THE SIGN STRUCTURE FOUNDATION WORK AREAS SHALL BE INCLUDED IN THE RELATED FOUNDATION WORK ITEMS AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIAN, SIDEWALK PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD AND DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH SECTION 252 AND 250 OF THE STANDARD SPECIFICATIONS RESPECTIVELY.
8. THE CONTRACTOR SHALL REMOVE ANY PROJECTING OBJECTS, SUCH AS BRACING OR FORM CLAMPS, THAT COULD CAUSE A DANGER TO THE MOTORING PUBLIC PRIOR TO RE-OPENING SHOULDERS.

8/1/2013 3:56:29 PM

8501 W. Higgins Road, Suite 200 Chicago, Illinois 60637 (773) 399-0112	USER NAME = 1485	DESIGNED - EF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	OVERHEAD SIGN STRUCTURE REPAIR & REPLACEMENT INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 2.0000' / 1" =	CHECKED - RS	REVISED -			VAR. 01 OVD SIN STR REPL14-30	VARIOUS	53	2	CONTRACT NO. 46291	
	PLOT DATE = 8/1/2013	DATE - 08/01/2013	REVISED -			SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			