SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY 0005					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4	4					
40600300	AGGREGATE (PRIME COAT)	TON	16	16					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	320	320					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	213	213					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	90	90					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	632	632					
42001300	PROTECTIVE COAT	SQ YD	300	300					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1750	1750					
42400800	DETECTABLE WARNINGS	SQ FT	250	250					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	7517	7517					
44000600	SIDEWALK REMOVAL	SQ FT	1750	1750					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY 0005					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	530	530					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	240	240					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	150	150					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	90	90					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	4	4					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1					
60255410	CATCH BASINS TO BE CLEANED	EACH	5	5					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1					
63500310	REMOVE AND REINSTALL DELINEATORS	EACH	20	20					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1604	1604					

* SPECIALITY ITEMS

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE =	CHECKED -	REVISED -
	PLOT DATE = 8/14/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ELEANOR ST.
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 1 OF 2 SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2921	2010-092-RS	COOK	18	3

CONTRACT NO. 60L89

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT