

URBAN

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY ITEMS 90% FEDERAL 10% STATE 0004	TRAFFIC SIGNALS			
					90% FEDERAL 6.7% STATE 3.3% BARTLETT 0021	90% FEDERAL 6.7% STATE 3.3% STREAMWOOD 0021	90% FEDERAL 10% STATE INTERCONNECT 0021	100% STREAMWOOD 0021
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER	TON	2048	2048				
	COURSE, 1L-19.0, N90							
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX	TON	317	317				
	"D", N50							
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE	TON	1910	1910				
	COURSE, MIX "F", N90							
42001300	PROTECTIVE COAT	SO YD	2913	2913				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5	SO FT	13966	13966				
	INCH							
42400800	DETECTABLE WARNINGS	SO FT	157	157				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	16253	16253				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	441	441				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1392	1392				
44004250	PAVED SHOULDER REMOVAL	SO YD	1017	1017				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	244	244				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	147	147				
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	98	98				
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY ITEMS 90% FEDERAL 10% STATE 0004	TRAFFIC SIGNALS			
					90% FEDERAL 6.7% STATE 3.3% BARTLETT 0021	90% FEDERAL 6.7% STATE 3.3% STREAMWOOD 0021	90% FEDERAL 10% STATE INTERCONNECT 0021	100% STREAMWOOD 0021
50102400	CONCRETE REMOVAL	CU YD	1	1				
50300225	CONCRETE STRUCTURES	CU YD	4.4	4.4				
50300300	PROTECTIVE COAT	SO YD	7.30	7.30				
50500505	STUD SHEAR CONNECTORS	EACH	18	18				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	580	580				
54213660	PRECAST REINFORCED CONCRETE FLARED END	EACH	1	1				
	SECTIONS 15"							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	419	419				
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	234	234				
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	313	313				
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	583	583				
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	1169	1169				
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	156	156				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	14	14				
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	701	701				
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	1094	1094				

\* SPECIALTY ITEMS  
 NON-PARTICIPATING ITEMS

FILE NAME =  
 USER NAME = g000011  
 DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -  
 PLOT SCALE = 1000000 / 1in  
 PLOT DATE = 4/4/2013

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 FAP 345/ US 20 (LAKE ST.)--OAK AVENUE TO PARK AVENUE  
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 345	SECTION 7Y-WRS	COUNTY COOK	TOTAL SHEETS 97	SHEET NO. 5
CONTRACT NO. 60N18				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				