

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX, HIGHWAY STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4-7	LOCATION MAP
8	SN 016-0623 VINCENNES ROAD OVER THORN CREEK - SITE PLAN
9	SN 016-0623 VINCENNES ROAD OVER THORN CREEK - EROSION PLAN
10	SN 016-0623 VINCENNES ROAD OVER THORN CREEK - CROSS SECTIONS
11	SN 016-0954 IL 83 AT LITTLE CALUMET RIVER - SITE PLAN
12	SN 016-0954 IL 83 AT LITTLE CALUMET RIVER - EROSION PLAN
13	SN 016-0954 IL 83 AT LITTLE CALUMET RIVER - CROSS SECTIONS
14	SN 016-2505 GOVERNOR'S HWY OVER BUTTERFIELD CREEK - SITE PLAN
15	SN 016-2505 GOVERNOR'S HWY OVER BUTTERFIELD CREEK - EROSION PLAN
16	SN 016-2505 GOVERNOR'S HWY OVER BUTTERFIELD CREEK - CROSS SECTIONS
17	SN 099-0241 RAMP IL 113 TO I-55 SB OVER CLAY POOL CREEK - SITE PLAN
18	SN 099-0241 RAMP IL 113 TO I-55 SB OVER CLAY POOL CREEK - EROSION PLAN
19	SN 099-0241 RAMP IL 113 TO I-55 SB OVER CLAY POOL CREEK - CROSS SECTIONS
20	SN 099-0276 US 52 OVER DUPAGE RIVER - SITE PLAN
21	SN 099-0276 US 52 OVER DUPAGE RIVER - EROSION PLAN
22	SN 099-0276 US 52 OVER DUPAGE RIVER - CROSS SECTIONS
23	SN 099-0295 IL 53 AT SUGAR CREEK - SITE PLAN
24	SN 099-0295 IL 53 AT SUGAR CREEK - EROSION PLAN
25	SN 099-0295 IL 53 AT SUGAR CREEK - CROSS SECTIONS
26	SN 099-2001 I-57 AT ROCK CREEK - SITE PLAN
27	SN 099-2001 I-57 AT ROCK CREEK - EROSION PLAN
28	SN 099-2001 I-57 AT ROCK CREEK - CROSS SECTIONS
29	SN 099-4618 IL 59 AT CLOW CREEK - SITE PLAN
30	SN 099-4618 IL 59 AT CLOW CREEK - EROSION PLAN
31	SN 099-4618 IL 59 AT CLOW CREEK - CROSS SECTIONS
32-34	DEWATERING SYSTEM DETAILS
35	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC 10)
36	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) (TC 14)
37	SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC 17)
38	ARTERIAL ROAD INFORMATION SIGNING (TC22)

HIGHWAY STANDARDS

STD. NO.	TITLE
04-701006	OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
03-701101	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
04-701201	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS + 45 MPH
04-701301	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
04-701400	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
07-701401	LANE CLOSURE, FREEWAY/EXPRESSWAY
07-701406	LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
05-701421	LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS + 45 MPH TO 55 MPH
02-701456	PARTIAL EXIT RAMP CLOSURE FREEWAY/EXPRESSWAY
08-701601	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
08-701606	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
08-701701	URBAN LANE CLOSURE, MULTILANE INTERSECTION
05-701801	LANE CLOSURE, MULTILANE, 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
02-701901	TRAFFIC CONTROL DEVICES

701001-02

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION) AT 8-1-1 OR (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES (48 HOUR NOTIFICATION IS REQUIRED).
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- ALL PERMITS AND FEES NEEDED TO OBTAIN ACCESS TO VARIOUS LOCATIONS FROM VILLAGE LAND OR FOREST PRESERVE WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AND INCIDENTAL TO THE COST OF THE STONE RIPRAP.
- EXCAVATION INTO THE STREAM BED FOR STONE RIPRAP INSTALLATION SHALL NOT BE DEEPER THAN THE BOTTOM OF THE FOOTING ON THE PIER OR ABUTMENT TO BE PROTECTED.
- DEBRIS REMOVAL, IF ENCOUNTERED, SHALL BE INCLUDED IN THE COST OF THE STONE RIPRAP.
- IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL DIMENSIONS & CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION ORDERING OF MATERIAL.
- THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE ARTERIAL TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.
- THE CONTRACTOR SHALL CONTACT THE DISTRICT EXPRESSWAY TRAFFIC CONTROL SUPERVISOR AT (847) 705-4155 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK ON I-55 OR I-57.

GENERAL NOTES

- ALL AREAS (INCLUDING WETLAND AREAS) OUTSIDE THE LIMITS OF RIPRAP PLACEMENT AND/OR EXCAVATION WHICH ARE DISTURBED (WHERE EXISTING SOIL CONTOURS HAVE BEEN ALTERED AND/OR EXISTING VEGETATION HAD BEEN DESTROYED BY THE CONTRACTORS OPERATIONS) SHALL BE RESTORED BY REGRADING TO THE ORIGINAL CONTOURS AND/OR SEEDING WITH SEEDING, CLASS 4, AND MULCHING WITH EROSION CONTROL BLANKETS. PLACE TEMPORARY SEEDING AND TEMPORARY EROSION CONTROL BLANKETS AS NEEDED. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT THE COSTS SHALL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICES FOR THE CONSTRUCTION ITEMS INVOLVED, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- ANY BRUSH AND TREE REMOVAL TO GET ACCESS SHOULD BE INCIDENTAL TO THE COST OF THE STONE RIPRAP.
- THE CONTRACTOR IS ADVISED TO AVOID OR MINIMIZE ANY DISTURBANCE TO EXISTING VEGETATION OUTSIDE THE LIMITS OF RIPRAP PLACEMENT AND CHANNEL EXCAVATION.
- THE CONTRACTOR MUST PROTECT PAVEMENT WHEN DUMPING RIPRAP ONTO PAVEMENT AND WILL BE RESPONSIBLE FOR RESTORING PAVEMENT MARKINGS.
- ANY GUARDRAIL OR SIGNS DAMAGED BY THE CONTRACTORS OPERATIONS SHALL BE REPLACED IN KIND AT THE CONTRACTORS EXPENSE.
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
- DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
- THE CONTRACTOR SHALL COMPLETE ALL WORK OVER THE SIDE OF THE BRIDGE USING DAYTIME LANE CLOSURES ONLY. NO OVERNIGHT LANE CLOSURES WILL BE ALLOWED WHEN THE CONTRACTOR IS NOT WORKING.
- THE CONTRACTOR SHALL SUBMIT DEWATERING AND SEDIMENT CONTROL PLANS FOR EACH SITE TO THE ENGINEER FOR APPROVAL.
- THE CONTRACTOR SHALL CONTACT THE ENGINEER AFTER DEWATERING FOR FINAL RIPRAP OR SLOPE MATTRESS PLACEMENT.
- UNLESS OTHERWISE NOTED, EXCAVATION OF MATERIAL REQUIRED TO INSTALL STONE RIPRAP SHALL BE INCLUDED IN THE ITEM BEING INSTALLED.
- THERE WILL BE NO PERMANENT OR OVERNIGHT LANE CLOSURES WILL BE ALLOWED ON ARTERIAL ROUTES FOR THIS CONTRACT (EXCLUDING LOCATIONS 4 AND 7).
- THIS PROJECT REQUIRES A US ARMY CORPS OF ENGINEERS (USACE) 404 PERMIT THAT WILL BE SECURED BY THE DEPARTMENT. AS A CONDITION OF THIS PERMIT, THE CONTRACTOR WILL NEED TO SUBMIT AN IN-STREAM WORK PLAN TO THE DEPARTMENT FOR APPROVAL. GUIDELINES ON ACCEPTABLE IN-STREAM WORK TECHNIQUES CAN BE FOUND ON THE USACE WEBSITE. THE USACE DEFINES AND DETERMINES IN-STREAM WORK. THE COST OF ALL MATERIALS AND LABOR NECESSARY TO COMPLY WITH THE ABOVE PROVISIONS TO PREPARE AND IMPLEMENT AN IN-STREAM WORK PLAN WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

3/12/2013 10:24:10 AM

Rev.