

SCHEDULE OF QUANTITIES

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"		
STA	OFFSET	EACH
301+69	51.5 LT	1
302+01	51.5 LT	1
TOTAL		2

AGGREGATE SUBGRADE IMPROVEMENT 12"		
FROM STA	TO STA	SQ YD
300+00	323+17	4,848
TOTAL		4,848

SEEDING, CLASS 3		
FROM STA	TO STA	ACRE
300+00	323+43	2.75
TOTAL		2.75

AGGREGATE BASE COURSE, TYPE B 8"		
FROM STA	TO STA	SQ YD
300+00	323+17	4,318
TOTAL		4,318

PIPE CULVERTS, CLASS A, TYPE 1 21"		
FROM STA.	TO STA.	FOOT
301+75	301+95	20
TOTAL		20

SIDEWALK REMOVAL		
FROM STA.	TO STA.	SQ FT
323+16	323+26	547
TOTAL		547

CONCRETE REMOVAL (SPECIAL)		
FROM STA.	TO STA.	SQ YD
314+92	315+07	16
TOTAL		16

PIPE CULVERT REMOVAL		
FROM STA	TO STA	FOOT
301+69	302+01	31
TOTAL		31

CURB REMOVAL AND REPLACEMENT		FOOT
LOCATION		
AT McCOY DRIVE		40
TOTAL		40

PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH		SQ FT
LOCATION		
AT McCOY		399
TOTAL		399

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH		SQ YD
LOCATION		
AT McCOY DRIVE		52
TOTAL		52

FILE NAME = Q:\DOT_25368367_US_34.ctb CN P:\Drawings-Advance Cont-A\Roadway\General\DI60183-Sht-Sched.Ldgn



USER NAME = URS	DESIGNED - MB	REVISED -
	DRAWN - KJB	REVISED -
PLOT SCALE = 50.0000' / in.	CHECKED - SPF	REVISED -
PLOT DATE = 5/13/2013	DATE - 5/13/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NTS SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	2012-0371	DUPAGE	45	9
			CONTRACT NO. 60T83	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				