

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN						
				ROADWAY	BRIDGE	BRIDGE	RETAINING WALL	HIGHWAY LIGHTING	TRAFFIC SIGNALS	
				0004 URBAN	0011 016-1713	0011 016-1716	0040 016-1802	0021 URBAN	0021 URBAN	
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	2991	2991						
35301200	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	305	305						
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	250	250						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.6	1.6						
40600300	AGGREGATE (PRIME COAT)	TON	8.3	8.3						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	197	197						
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	416	416						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	339	339						
42001200	PAVEMENT FABRIC	SQ YD	3296	3296						
42001300	PROTECTIVE COAT	SQ YD	1986	1986						
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	110	110						
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	141	141						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	7150.5	7150.5						
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	1832.5	1832.5						

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

Rev. 10-30-13



DIG0V26-sh1-500.dgn
 USER NAME = ehua
 PLOT SCALE = 1/8" = 1' / in.
 PLOT DATE = 9/16/2013

DESIGNED - JWM
 DRAWN - JWM
 CHECKED - DBM
 DATE - 9/15/13

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE: SHEET 3 OF 26 SHEETS STA. TO STA.

F.A.I. RTE. 90/94/290	SECTION 2013-008R	COUNTY COOK	TOTAL SHEETS 559	SHEET NO. 8
CONTRACT NO. 60W26			ILLINOIS FED. AID PROJECT	

FILE PATH : \\138629-projects\asosonline\local\AECOM\Documents\01-Americas\Transportation\60W26\Sheet\60W26-Contract\VIEW26-sh1-500.dgn