90% FED 10% STATE

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY (URBAN) | CONSTRUCTION CODE: ROADWAY 0004 URBAN | BRIDGE 0011 016-1713 | BRIDGE 0011 016-1716 | RETAINING WALL 0040 016-1802 | HIGHWAY LIGHTING 0021 URBAN | TRAFFIC SIGNALS 0021 URBAN |
|---|---|---|---|---|---|---|---|---|---|
| 50300225 | CONCRETE STRUCTURES | CU YD | 2777.9 | 100 △1 | 426 | 2081.9 | 170 △1 | | |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 2811.8 | | 1076 | 1699.8 | 36 | | |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 5122 | | 1643 | 3479 | | | |
| 50300285 | FORM LINER TEXTURED SURFACE | SQ FT | 4224 | | 1244 | 2980 | | | |
| 50300300 | PROTECTIVE COAT | SQ YD | 8251 | | 3079 | 5172 | | | |
| 50500105 | FURNISHING AND ERECTING STRUCTURAL STEEL | L SUM | 1 | | 0.51 | 0.49 | | | |
| 50500505 | STUD SHEAR CONNECTORS | EACH | 38001 | | 8622 | 29379 | | | |
| 50800105 | REINFORCEMENT BARS | POUND | 1,569,250 | | 566,610 | 545,430 | 457,210 △1 | | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 1,009,290 | 113,880 | 306,660 | △1 574550 | 14,200 △1 | | |
| 50800515 | BAR SPLICERS | EACH | 2275 | | 144 | 2131 | | | |
| 50800530 | MECHANICAL SPLICERS | EACH | 1000 | | 456 | | 544 △1 | | |
| 51100100 | SLOPE WALL 4 INCH | SQ YD | 50 | | 50 | | | | |
| 51500100 | NAME PLATES | EACH | 3 | | 1 | 1 | 1 | | |
| 51602000 | PERMANENT CASING | FOOT | 2374 △1 | | 460 | 1914 △1 | | | |

* DENOTES SPECIALTY ITEM  ** DENOTES NON-PARTICIPATING ITEM

△1 Rev. 10-30-13

AECOM
303 EAST WACKER DRIVE, SUITE 1400
CHICAGO, IL 60601-5276
PHONE: (312) 373-7700 FAX: (312) 373-6800

| | | | |
|---|---|---|---|
| 0160W26-sht-500.dgn | DESIGNED - JWM | REVISED - | |
| USER NAME = chiua | DRAWN - JWM | REVISED - | |
| PLOT SCALE = 1.0000 ' / in. | CHECKED - DBM | REVISED - | |
| PLOT DATE = 9/16/2013 | DATE - 9/15/13 | REVISED - | |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 5 OF 26 SHEETS | STA. TO STA.

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 90/94/290 | 2013-008R | COOK | 559 | 10 |

CONTRACT NO. 60W26

ILLINOIS FED. AID PROJECT

FILE PATH = pw:\\388239-pwint1.aecomonline.local:PWAECOM20\Documents\01 Americas\Transportation\60269938 Circle\Phase_II\000_CAD\006_Roadway\Sheets\60W26_Contract\0160W26-sht-500.dgn