

90% FED 10% STATE

CONSTRUCTION CODE

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY 0004 URBAN	BRIDGE 0011 016-1713	BRIDGE 0011 016-1716	RETAINING WALL 0040 016-1802	HIGHWAY LIGHTING 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	
X6060714	CONCRETE MEDIAN (SPECIAL)	SO FT	252	252						
* X6331110	STEEL POSTS, SPECIAL	EACH	4	4						
X6370050	CONCRETE BARRIER WALL (SPECIAL)	FOOT	448	448						
X6370700	CONCRETE BARRIER TRANSITION (SPECIAL)	FOOT	105	105						
X6430120	REMOVE IMPACT ATTENUATORS, NO SALVAGE	EACH	1	1						
X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	310	310						
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	12	12						
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1						
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1						
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	115	115						
X7040010	TEMPORARY CONCRETE BARRIER (SPECIAL)	FOOT	737.5	737.5						
* X7200105	SIGN PANEL - TYPE I (SPECIAL)	SO FT	46	46						
* X7360300	REMOVE OVERHEAD SIGN STRUCTURE - WALKWAY	FOOT	69	69						
* X8510250	PAINT EXISTING POLE, POST OR CONTROLLER COMPLETE	EACH	7						7	
* X8800101	PEDESTRIAN PUSH-BUTTON, SPECIAL	EACH	2							2

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

Rev. 10-30-13



D:\60626-shc-500.dgn
 USER NAME = chuo
 PLOT SCALE = 1/8000" = 1' in.
 PLOT DATE = 9/16/2013

DESIGNED - JWM
 DRAWN - JWM
 CHECKED - DBM
 DATE - 9/15/13

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 22 OF 26 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-008R	COOK	559	27
CONTRACT NO. 60W26				
ILLINOIS FED. AID PROJECT				

FILE PATH: c:\1388939\p\mst\mst\mst\local\p\60626\Documents\01_AmericanTransportation\60626\60626_Cur\14\Phase 1\US02_C01\006_Boards\Sheet\60626-11-500.dgn