

**SIGNING SCHEDULE**

LOCATION	SIGN NO.	LEGEND / DESCRIPTION	CODE	ACTION	LOCATION (STATION / OFFSET)		EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		NUMBER OF POSTS	TELESCOPING STEEL SIGN SUPPORT (FT)	STRUCTURAL STEEL SIGN SUPPORT - BREAKWAY (LBS)	STEEL POST, SPECIAL (EACH)	REMOVE GROUND MOUNTED SIGN SUPPORT (EACH)	REMOVE CONCRETE FOUNDATION - GROUND MOUNT (EACH)	CONCRETE FOUNDATIONS (CU)	WOOD SIGN SUPPORT (FT)
					EXISTING	PROPOSED	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)								
HALSTED STREET	NB-01-SP	PEDESTRIAN CROSSING	W11-2	REMOVE	3830+31.19	42.3' RT	-	-	2.50	2.50								
	NB-02-SA	STREET NAME OVERHEAD - HARRISON	D3-2D/F	REMOVE AND REPLACE SIGN	3831+34.32	37.9' RT	3831+63.42	14.2' RT	5.50	1.50	5.50	1.50						
	NB-03-ST	CTA BUS STOP		REMOVE AND REPLACE SIGN (SEE NOTE 1)	3832+87.41	29.7' RT	(BY OTHERS)		1.50	2.00	1.50	2.00			1	1		
	NB-04A-LP	BIKE ROUTE - NORTH TO DEPAUL	D11-1	REMOVE AND REPLACE SIGN	3833+58.11	29.7' RT	-	-	2.00	1.50	-	-						
	NB-04B-LP	BIKE LANE	R3-17	PROPOSED SIGN	-	-	3833+85.00	41.3' RT	-	-	2.00	1.50						
	NB-05-LP	NO PARKING / BUS STOP / TOW ZONE / LEFT ARROW OR RIGHT ARROW	R7-207-1/3	REMOVE AND REPLACE SIGN	3833+58.11	29.7' RT	3833+85.00	41.3' RT	1.50	1.50	1.50	1.50						
	NB-06-LP	NO PARKING / BUS STOP / TOW ZONE / LEFT ARROW OR RIGHT ARROW	R7-207-1/3	REMOVE AND REPLACE SIGN	3837+82.96	29.5' RT	3837+85.00	41.3' RT	1.50	1.50	1.50	1.50						
	NB-07-ST	ONLY LEFT / THROUGH RIGHT	R3-8R	REMOVE AND REPLACE SIGN	3838+38.34	29.9' RT	3838+38.46	32.7' RT	2.50	2.50	2.50	3.00	1		1			
	NB-08-SP	BIKE LANE	R3-17	PROPOSED SIGN	-	-	3839+11.50	33.6' RT	-	-	2.00	1.50						
	NB-09-SP	ENDS	R3-17bP	PROPOSED SIGN	-	-	-	-	-	-	2.00	0.67						
	SB-01-SA	STREET NAME OVERHEAD - HARRISON	D3-2D/F	REMOVE AND REPLACE SIGN	3830+34.58	36.1' LT	3830+28.24	7.6' LT	5.50	1.50	5.50	1.50						
	SB-02-ST	UIC CAMPUS	CUSTOM	EXISTING SIGN TO REMAIN	3831+66.81	71.7' LT	-	-	3.58	8.75								
	SB-03-LP	NO PARKING	R7-201-4	REMOVE AND REPLACE SIGN	3833+57.81	26.9' LT	3832+90.00	33.3' LT	1.50	1.50	1.50	1.50						
	SB-04-ST	CTA BUS STOP		REMOVE AND REPLACE SIGN (SEE NOTE 1)	3835+29.12	25.5' LT	(BY OTHERS)		1.50	2.00	1.50	2.00			1	1		
	SB-05-ST	CTA BLUE LINE	CUSTOM	EXISTING SIGN TO REMAIN	3835+41.01	38.6' LT	-	-	0.42	1.42								
	SB-06-LP	NO PARKING / BUS STOP	R7-207-4	REMOVE AND REPLACE SIGN	3835+54.31	25.1' LT	3836+03.00	33.3' LT	1.50	1.50	1.50	1.50						
	SB-07-LP	SHARED LANE YIELD TO BIKES		REMOVE	-	-	-	-	2.00	2.00								
	SB-08-LP	NO PARKING	R7-201-4	REMOVE AND REPLACE SIGN	3837+82.52	25.6' LT	3838+25.00	26.8' LT	1.50	1.50	1.50	1.50						
SB-09-WP	MANAGEMENT IS NOT RESPONSIBLE FOR THEFT OR DAMAGE TO VEHICLES OR CONTENTS	CUSTOM	EXISTING SIGN TO REMAIN	3838+39.42	35.9' LT	-	-	1.00	1.50									
SB-10-ST	GIORDANOS PRIVATE PROPERTY	CUSTOM	EXISTING SIGN TO REMAIN	3838+69.18	32.1' LT	-	-	1.00	1.50									
SB-11-SP	BIKE LANE	R3-17	PROPOSED SIGN	-	-	3839+98.48	23.2' LT	-	-	2.00	1.50							
SB-12-SP	AHEAD	R3-17aP	PROPOSED SIGN	-	-	-	-	-	-	2.00	0.67							
HARRISON STREET	EB-01-ST	RIGHT LANE MUST TURN RIGHT	R3-7	PROPOSED SIGN	-	-	7800+02.11	32.8' RT	-	-	2.50	2.50	1		1			
	EB-02-LP	CTA BUS STOP		REMOVE AND REPLACE SIGN (SEE NOTE 1)					1.50	2.00	1.50	2.00						
	EB-03-LP	TO	M4-5	REMOVE AND REPLACE SIGN					2.00	1.00	2.00	1.00						
	EB-04-LP	90 (M1-1)	M1-1	REMOVE AND REPLACE SIGN	7805+28.68	30.9' RT	7805+28.68	30.9' RT	2.00	2.00	2.00	2.00						
	EB-05-LP	94 (M1-1)	M1-1	REMOVE AND REPLACE SIGN					2.00	2.00	2.00	2.00						
	EB-06-LP	ARROW (M6-1)	M6-1	REMOVE AND REPLACE SIGN					1.75	1.25	1.75	1.25						
	EB-07-SP	RIGHT TURN ONLY	R3-5R	PROPOSED SIGN	-	-	7805+78.88	34.2' RT	-	-	2.50	3.00						
	EB-08-SP	HONORARY - JANE ADDAMS HULL-HOUSE ST	D3-3	REMOVE AND REPLACE SIGN	7806+06.48	65.2' LT	7806+07.93	71.4' RT	3.00	0.50	3.00	0.50						
	EB-09-SP	HONORARY - FRANK REED HORTON WAY	D3-3	REMOVE AND REPLACE SIGN					3.00	0.50	3.00	0.50						
	EB-10-SA	STREET NAME OVERHEAD - HALSTED	D3-2D/F	REMOVE AND REPLACE SIGN	7807+03.86	34.0' RT	7807+03.94	11.9' RT	5.00	1.50	5.00	1.50						
	EB-100-LP	NO PARKING	R7-201-4	REMOVE AND REPLACE SIGN	7809+83.12	33.1' RT	7809+95.42	34.2' RT	1.50	1.50	1.50	1.50						
	EB-101-TS	STOP SIGN	R1-1	REMOVE AND REPLACE SIGN	7810+81.00	26.0' RT	7810+81.00	38.1' RT	2.50	2.50	2.50	2.50	14.50					
WB-01-LP	NO PARKING / BUS STOP / TOW ZONE / LEFT ARROW	R7-207-3	REMOVE AND REPLACE SIGN	7805+28.45	33.3' LT	7805+28.45	33.3' LT	1.50	1.50	1.50	1.50							
WB-02-SA	STREET NAME OVERHEAD - HALSTED	D3-2D/F	REMOVE AND REPLACE SIGN	7805+95.15	40.4' LT	7805+64.11	16.8' LT	5.00	1.50	5.00	1.50							
WB-100-LP	NO PARKING	R7-201-4	REMOVE AND REPLACE SIGN	7809+84.45	33.5' LT	7809+90.33	34.2' LT	1.50	1.50	1.50	1.50							
ROUNDED SUBTOTAL												15	0	4	2	0	0	0

NOTES:

- SIGN PANEL TO BE REMOVED AND REPLACED BY THE CTA. CONTRACTOR SHALL COORDINATE WITH THE CTA PRIOR TO REMOVING AND INSTALLING THE GROUND MOUNTED SIGN SUPPORT OR LIGHT POLE.
- FOR MOUNTING TYPE AND REFLECTIVITY SEE SHEET 185.
- FOR TOTAL QUANTITIES SEE SHEET 184A.



D160W26-sht-Sign-Schedule-02  
 USER NAME = chiu  
 PLOT SCALE = 50.0000' / in.  
 PLOT DATE = 9/12/2013

DESIGNED - OPS  
 DRAWN - OPS  
 CHECKED - DBM  
 DATE - 9/15/13

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SIGNING SCHEDULE

SCALE: SHEET 2 OF 5 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-008R	COOK	559	184
CONTRACT NO. 60W26				
ILLINOIS FED. AID PROJECT				

FILE PATH = p:\388035-p\m\escomon\me\local\p\MECD\000\Documents\01\_Americas\Transportation\60269938\_Circle\Phase\_1\1600\_CAD\005\_Roadway\Sheets\60W26-sht-Sign-Schedule-02