



8/15/2013 10:27:35 AM c:\pwworking\acocom00\myer.sc\d0207895.DIG0W26-sht-Light-09.dgn

- "D" PROVIDE 3-1/2" NO. 6 AERIAL CABLES WITH MESSENGER WIRE. SEE NOTE 2
- "E" EXISTING TO REMAIN
- "F" REMOVE AND SALVAGE EXISTING STEEL POLE, LUMINAIRE, MAST ARM AND BALLAST HOUSING. BREAKDOWN CONCRETE FOUNDATION COMPLETE.
- "F1" REMOVE AND SALVAGE EXISTING LIGHT POLE, LUMINAIRE AND MAST ARM COMPLETE.
- "G" REMOVE LUMINAIRE(S) AND MAST ARM(S). ANCHOR BASE STEEL POLE AND CONCRETE FOUNDATION TO BE REMOVED WITH TRAFFIC SIGNAL WORK.
- "P" REMOVE EXISTING MANHOLE COMPLETE

**NOTES:**

1. THE EXISTING CDOT CONDUITS ATTACHED TO THE UNDERSIDE OF THE BRIDGE STRUCTURE MAY CONTAIN ASBESTOS MATERIALS. THE CONDUITS SHALL BE REMOVED AND DISPOSED OF PROPERLY PRIOR TO THE BRIDGE DEMOLITION. CONDUITS TESTED AND CONFIRMED TO CONTAIN ASBESTOS MUST BE REMOVED IN ACCORDANCE WITH THE SPECIAL PROVISION "REMOVAL OF ASBESTOS CEMENT CONDUIT". ASBESTOS CONDUIT REMOVAL SHALL BE PAID FOR UNDER THE "REMOVAL OF ASBESTOS CEMENT CONDUIT" PAY ITEM.
2. THE LIGHTING ON THE WEST SIDE OF THE BRIDGE MUST BE KEPT OPERATIONAL DURING STAGE I OF THE BRIDGE RECONSTRUCTION. IF REQUIRED, INSTALL TEMPORARY AERIAL CABLES TO PROVIDE TEMPORARY POWER TO THE LIGHTING CIRCUITS ALONG THE WEST SIDE OF THE HALSTED STREET BRIDGE DURING STAGED CONSTRUCTION. THE ENGINEER SHALL DETERMINE IF THE TEMPORARY AERIAL CABLES ARE REQUIRED. THE CONTRACTOR SHALL NOT INSTALL THE AERIAL CABLES WITHOUT PRIOR APPROVAL FROM THE ENGINEER. THE AERIAL CABLES SHALL BE REMOVED WHEN THE LIGHTING UNITS ON THE WEST SIDE ARE REMOVED AND SALVAGED. THE COST TO REMOVE AND DISPOSE OF THE TEMPORARY AERIAL CABLES WILL NOT BE PAID FOR SEPARATELY AND SHALL BE INCLUDED IN THE "AERIAL CABLE, 3-1/2" NO. 6 WITH MESSENGER WIRE" PAY ITEM.

FOR CONDUIT AND FOUNDATION PLANS  
SEE DRAWING NO. E-07.

FOR LIGHTING CABLE AND EQUIPMENT  
INSTALLATION PLANS SEE DRAWING NO. E-08.

<b>CITY OF CHICAGO</b> DEPARTMENT OF TRANSPORTATION DIVISION OF ENGINEERING	
<b>AECOM</b>	
WORK ORDER NO. _____	DATE _____
COST ALLOCATION ACCOUNT _____	
APPROPRIATION ACCOUNT _____	MATERIAL _____
	LABOR _____
<b>HALSTED STREET LIGHTING REMOVAL PLAN</b>	
<b>CITY OF CHICAGO</b> DEPT. OF TRANSPORTATION DIVISION OF ELECTRICAL OPERATIONS	
DRAFTSMAN: CAM	ENGINEER: WDS
SUPERVISING ENGINEER: WDS	ELEC. DESIGN ENGR. WDS
ENGINEER OF ELECTRICITY:	
GEN'L SUPT. OF ELECTRICITY:	
DEPUTY COMMISSIONER:	
SIZE: 22"   34"	SCALE: 1" = 30'
DATE: 08/20/13	DATE: 8/20/13
C.D.O.T. PROJECT NO.:	DWG. NO.:
	9 OF 22

E-09