



- "E" EXISTING TO REMAIN
- "F" REMOVE AND SALVAGE EXISTING STEEL POLE, LUMINAIRE, MAST ARM AND BALLAST HOUSING. BREAKDOWN CONCRETE FOUNDATION COMPLETE.
- "F1" REMOVE AND SALVAGE EXISTING STEEL POLE, LUMINAIRE AND MAST ARM.
- "G" REMOVE LUMINAIRE AND MAST ARM, ANCHOR BASE STEEL POLE AND CONCRETE FOUNDATION TO BE REMOVED WITH TRAFFIC SIGNAL WORK.
- "P" REMOVE EXISTING MANHOLE COMPLETE

**NOTES:**

- THE EXISTING CDOT CONDUITS ATTACHED TO THE UNDERSIDE OF THE BRIDGE STRUCTURE MAY CONTAIN ASBESTOS MATERIALS. THE CONDUITS SHALL BE REMOVED AND DISPOSED OF PROPERLY PRIOR TO THE BRIDGE DEMOLITION. CONDUITS TESTED AND CONFIRMED TO CONTAIN ASBESTOS MUST BE REMOVED IN ACCORDANCE WITH THE SPECIAL PROVISION "REMOVAL OF ASBESTOS CEMENT CONDUIT". ASBESTOS CONDUIT REMOVAL SHALL BE PAID FOR UNDER THE "REMOVAL OF ASBESTOS CEMENT CONDUIT" PAY ITEM.



DATE	REVISION

CITY OF CHICAGO  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF ENGINEERING



WORK ORDER NO. \_\_\_\_\_ DATE \_\_\_\_\_  
 COST ALLOCATION ACCOUNT \_\_\_\_\_  
 APPROPRIATION ACCOUNT MATERIAL \_\_\_\_\_ LABOR \_\_\_\_\_

HARRISON STREET  
LIGHTING REMOVAL PLAN

CITY OF CHICAGO  
DEPT. OF TRANSPORTATION  
DIVISION OF ELECTRICAL OPERATIONS

DRAFTSMAN: CAM	CHIEF DRAFTSMAN: WDS	ENGINEER: WDS
SUPERVISING ENGINEER: WDS	ELEC. DESIGN ENGR. WDS	

ENGINEER OF ELECTRICITY:	<b>E-12</b>
GEN'L SUPT. OF ELECTRICITY:	
DEPUTY COMMISSIONER:	

FOR CONDUIT AND FOUNDATION PLANS  
SEE DRAWING NO. E-10.  
  
 FOR LIGHTING CABLE AND EQUIPMENT  
INSTALLATION PLANS SEE DRAWING NO. E-11.

8/15/2013 11:59:52 AM c:\pwworking\aecom\00\myer.sc\d0207895\DIG0W26-sht-Light-12.dgn