



TOP OF SEAT ELEVATION

Girder No.	Seat Elevation
1	594.23
2	594.23
3	594.23
4	594.39
5	594.51
6	594.64
7	594.77
8	594.89
9	595.02
10	595.15
11	595.28
12	595.40
13	595.53
14	595.62
15	595.70

Notes:
 Four steps monolithically with cap.
 Space reinforcement in cap to miss anchor bolts.
 For Sections A-A, B-B and C-C, see sheet S2-68 of S2-81.
 Backfill shall be placed behind the abutment after the superstructure has been poured and false work removed. See Article 502.10 of the Standard Specifications.

4:33:58 PM 0161716-60W26-S067-Pier4_P&E.dgn



USER NAME = rlschultz	DESIGNED - JRM	REVISED
PLOT SCALE = 4:0.0005 ' / in.	CHECKED - MDS	REVISED
PLOT DATE = 9/15/2013	DRAWN - RLS	REVISED
	CHECKED - JRM	REVISED

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

PIER 4 PLAN AND ELEVATION
 STRUCTURE NO. 016-1716

SHEET NO. S2-67 OF S2-81 SHEETS

F.A.U. R.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3730	2013-008R	COOK	559	427
CONTRACT NO.			60W26	
ILLINOIS FED. AID PROJECT				