CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
				CONSTRUCTION CODE 0021																							
				TRAFFIC SIGNAL																							
				URBAN																							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																							
67100100	MOBILIZATION	L SUM	1	1																							
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																							
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	64	28	1	1	1		2	1	2	1	1	1	2	5	2	2	5	1	1	1	1	1	1	1	2
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	86	32							6	3	3			14			2	5		2	4	2	2	4	7
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	47	21	4					2	4	3	2			6			3						2		
88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	4																1	2							1
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	5	2																2							1
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	42	16							2	1	2			8				2		1	4	2			4
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	107	48	4					2	4	1	1			10			4	2		2	4	6	3	8	8
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	12	3						1	2	1							3			1			1		
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	8	3																				2		2	1
88030230	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	4	2															1								1
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	47	23	4					1	2		1			6			4			2			3		1

Rev. 10-28-13

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - PKC	REVISED -
		DRAWN - EA, EB, WC	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - PKC	REVISED -
	PLOT DATE = $DATE$	DATE - 8/15/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
(SHEET 3 OF 5)

SCALE: N.T.S. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.B. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2013-040TS	COOK	84	07
		CONTRACT NO. 60W85		

FED. ROAD DIST. NO. . | ILLINOIS | FED. AID PROJECT