



THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACTOR'S BID PRICE.

- 6 EACH SIGNAL HEAD, 1-FACE, 3-SECTION, MAST ARM MOUNTED
- 3 EACH SIGNAL HEAD, 1-FACE, 3-SECTION, BRACKET MOUNTED
- 1 EACH SIGNAL HEAD, 1-FACE, 5-SECTION, BRACKET MOUNTED
- 2 EACH SIGNAL HEAD, 1-FACE, 5-SECTION, MAST ARM MOUNTED
- 1 EACH SIGNAL HEAD, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED
- 8 EACH TRAFFIC SIGNAL BACKPLATE

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "EAGLE" TO MATCH THE EXISTING ADJACENT SYSTEM.

| | | | | | | | | | | | | | | |
|--------------------------|----------------------|------------------|-----------|---|--|-----------|----|-------------|---------|--------|--------------|---|----|----|
| FILE NAME = \$FILEL\$ | USER NAME = \$USER\$ | DESIGNED - PKG | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | TRAFFIC SIGNAL MODIFICATION PLAN GRAND AVENUE AT NORTHWEST AVENUE | | | F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | | |
| | | DRAWN - EA | REVISED - | | SCALE: 1"=20' | SHEET NO. | OF | SHEETS | STA. | TO | STA. | 1376 | 24 | 16 |
| | | CHECKED - PKG | REVISED - | | | | | | | | | CONTRACT NO. 60W98 | | |
| | | DATE - 8/15/2013 | REVISED - | | | | | | | | | FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT | | |