

TEMPORARY PAVEMENT MARKING SCHEDULE						
LOCATION	TEMPORARY PAVEMENT MARKING					WORK ZONE REMOVAL (SQ FT)
	L & S	4"	6"	8"	12"	
PRESTAGE 1						
IL 173		5,290		579		
PRESTAGE 1A						
IL 173	219	9,332		1,333		76 4,374
WINTER SHUT-DOWN 2013						
IL 173		3,989				1,329
FOREST HILLS ROAD		3,237				1,095
STAGE 1						
IL 173	865	33,529		3,145	740	227
FOREST HILLS ROAD	187	17,048		391		78
PERRYVILLE ROAD	206	6,931		799		67
STAGE 1A						
KIMBER DRIVE		275				92
BURDEN ROAD		1,421				467
MENARDS		450				150
KRASSE DRIVE		799				266
PERRYVILLE ROAD		1,445				482
STAGE 1B						
IL 173		899				378
PERRYVILLE ROAD	208	7,379		599		3,040
STAGE 1C						
CONTINENTAL DRIVE		145				48
FOREST HILLS ROAD		205				68
PERRYVILLE ROAD		1,163				387
PRESTAGE 2						
CONTINENTAL	32	254				117
KIMBER DRIVE		175				58
PRESTAGE 2A						
CONTINENTAL	115	678		417		602
KIMBER DRIVE		228				76
STAGE 2						
IL 173	749	27,359		5,672		366 14,382
KIMBER DRIVE	193	673		360		67 805
BURDEN ROAD	63	390		282		45 471
MENARDS						18 36
KRASSE DRIVE	42	353		180		56 392
FOREST HILLS ROAD	125	13,988		374		71 5,182
PERRYVILLE ROAD	208	6,950		620		56 3,050
SPEEDWAY		516				172

TEMPORARY PAVEMENT MARKING SCHEDULE						
LOCATION	TEMPORARY PAVEMENT MARKING					WORK ZONE REMOVAL (SQ FT)
	L & S	4"	6"	8"	12"	
STAGE 2						
IL 173	749	27,359		5,672		366 14,382
KIMBER DRIVE	193	673		360		67 805
BURDEN ROAD	63	390		282		45 471
MENARDS						18 36
KRASSE DRIVE	42	353		180		56 392
FOREST HILLS ROAD	125	13,988		374		71 5,182
PERRYVILLE ROAD	208	6,950		620		56 3,050
SPEEDWAY		516				172
STAGE 2A						
IL 173		1,871				557
SPEEDWAY		505				188
CONTRACTORS DRIVE		1,276				423
PERRYVILLE ROAD		989				330
STAGE 2B						
PERRYVILLE ROAD	208	7,480		520		45 3,143
STAGE 2C						
PERRYVILLE ROAD		1,329				443
STAGE 3						
IL 173	2,868	11,448	3,126	17,688		721 572
CONTINENTAL DRIVE	234	676	57	459		84
KIMBER DRIVE	266	916	17	510		84
BURDEN ROAD	126	340		234		30
FOREST HILLS ROAD	671	12,717	779	3,449		252 636
KRASSE DRIVE	42	354		177		96
SPEEDWAY EAST				177		16
SPEEDWAY NORTH						18
PERRYVILLE ROAD	376	6,745	943	1,878		132 337
WINTER SHUT-DOWN 2014						
IL 173	437	9,782		3,154	2,313	165 9,639
PERRYVILLE ROAD	219	7,408		1,143	413	168 3,979
STAGE 4						
IL 173	130	8,135		712		78 3,472
STAGE 5						
IL 173	208	27,537		5,436		93 13,197
PERRYVILLE ROAD	104	179				464
MITCHELL ROAD	78	1,852		182	38	30 901
STAGE 6						
IL 173	842	22,374	5,362	5,957		231 1,119
TOTALS	11,180	319,048	10,284	65,693	3,504	4,071 101,150

PAVEMENT MARKING REMOVAL		
DESCRIPTION / LOCATION	(FT)	(SQ FT)
ILLINOIS ROUTE 173		
LETTERS AND SYMBOLS		1,022
SOLID 4"	15606	5,202
SOLID 6"	1563	762
SOLID 8"	8211	5,474
SOLID 12"	1628	1,828
SOLID 24"	361	722
CONTINENTAL DRIVE		
LETTERS AND SYMBOLS		117
SOLID 4"	338	113
SOLID 6"	28	14
SOLID 8"	230	153
SOLID 24"	42	84
KIMBER DRIVE		
LETTERS AND SYMBOLS		133
SOLID 4"	458	153
SOLID 6"	8	4
SOLID 8"	255	170
SOLID 12"	1628	1,828
SOLID 24"	42	84
BURDEN ROAD		
LETTERS AND SYMBOLS		62
SOLID 4"	170	57
SOLID 8"	117	78
SOLID 24"	15	30
FOREST HILLS ROAD		
LETTERS AND SYMBOLS		336
SOLID 4"	6358	2,119
SOLID 6"	399	195
SOLID 8"	1725	1,150
SOLID 12"	71	71
SOLID 24"	120	252
KRASSE DRIVE		
LETTERS AND SYMBOLS		21
SOLID 4"	177	59
SOLID 8"	89	58
SOLID 24"	45	90
PERRYVILLE ROAD		
LETTERS AND SYMBOLS		197
SOLID 4"	3373	1,124
SOLID 6"	472	236
SOLID 8"	839	559
SOLID 24"	66	132
TOTAL		24,300



70300100 SHORT TERM PAVEMENT MARKING		
STAGE	LENGTH (FT)	DESCRIPTION
Pre 1	1,500	
1	1,000	
2	3,500	
3	1,500	
4	1,000	
5	3,500	
6	1,500	
TOTAL	13,500	

THE QUANTITY PROVIDED IS ESTIMATED AND CAN BE USED WITH APPROVAL OF THE ENGINEER IN SITUATIONS WHERE SHORT TERM MARKINGS MAKE MORE SENSE THAN TEMPORARY PAVEMENT MARKINGS.

FILE NAME : SAP\projects\2012\085142-05-S10005 Upchurch, Lousa Park 02 Ph ILL\Cap\TADD Sweets\2007\33\CR - 5013.dgn
 MODEL : MODEL 3
 PLOT DRIVER : EPL\DRV54



USER NAME : rgoe@ez	DESIGNED - RG	REVISED -
PLOT SCALE : 20.0000 / in.	DRAWN - TRF	REVISED -
PLOT DATE : 9/17/2013	CHECKED - CMS	REVISED -
	DATE - APRIL 30, 2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 303	SECTION 129R	COUNTY WINNEBAGO	TOTAL SHEETS 968	SHEET NO. 116
CONTRACT NO. 64988				
FED. ROAD DIST. NO. 2 [ILLINOIS] FED. AID PROJECT				

REV. 9-21-13