

EARTHWORK – PRESTAGE

LOCATION		20200100	20300100	20300200			20400800	21101505
		EARTH EXCAVATION (CUT)	CHANNEL EXCAVATION	ROCK EXCAVATION IN CHANNEL	EARTH EXCAVATION ADJUST SHRINKAGE 25% EARTH	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)*	TOPSOIL EXCAVATION AND PLACEMENT
STATION TO STATION		CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
PRESTAGE								
IL 173 - RT								
1022+07.90	1027+00	352	0	0	264	44	220	0
1027+00	1033+00	420	0	0	315	76	239	0
1033+00	1039+00	632	0	0	474	55	419	0
1039+00	1045+00	1297	0	0	972	52	921	0
1045+00	1051+00	596	0	0	447	52	395	0
1051+00	1057+00	670	0	0	503	368	135	0
1057+00	1063+00	416	0	0	312	170	142	0
1063+00	1069+50	373	0	0	279	3	276	0
IL 173 - LT **								
1078+00	1084+00	25	961	0	740	5730	-4991	393
1084+00	1090+00	0	0	0	0	6513	-6513	263
1090+00	1093+00	0	0	0	0	4055	-4055	148
1093+00	1099+00	0	0	0	0	8561	-8561	309
1099+00	1105+00	0	0	0	0	7356	-7356	287
1105+00	1111+00	0	0	0	0	7512	-7512	295
1111+00	1117+00	1	1286	0	965	9538	-8573	573
1117+00	1123+00	0	20657	11214	23903	5916	17987	598
1123+00	1129+00	0	4380	0	3285	8559	-5274	713
1129+00	1135+00	0	6313	0	4735	6787	-2052	705
1135+00	1141+00	0	2237	0	1678	10430	-8752	716
1141+00	1142+88.00	26	0	0	20	1959	-1939	95
FOREST HILLS ROAD - LT								
376+10	380+00	167	0	0	125	133	-8	0
380+00	385+50	158	0	0	119	1102	-984	0
385+50	391+50	310	0	0	233	340	-108	0
391+50	394+00	60	0	0	45	81	-36	0
394+00	399+00	58	0	0	44	26	18	0
456+50	459+00	104	0	0	78	5	73	0
459+00	465+00	214	0	0	161	438	-278	0
465+00	469+48	248	0	0	186	665	-479	0
TOTAL		6127	35834	11214	39881	86525	-46644	5095

* 20400800 FURNISHED EXCAVATION

** COMPLETE BULK EARTHWORK IN PRESTAGE AND THE REMAINDER IN STAGE 4

FILE NAME = ...\\CADD SHEETS\Z00793CVR-S012.dgn	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES EARTHWORK – PRESTAGE	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
THE UPCHURCH GROUP, INC.	PLOT SCALE = 2.0000' / IN.	DRAWN - JAU	REVISED -			303	129R	WINNEBAGO	968	50	
PLOT DATE = 5/3/2013 3:03:36 PM	DATE - APRIL 30, 2013	CHECKED - RLH	REVISED -			SCALE:		SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT	
		DATE - APRIL 30, 2013	REVISED -			CONTRACT NO. 64988					