EARTHWORK - STAGE 1

		20200100	20300100	20300200			20400800	21101505
LOCAT	TION	EARTH EXCAVATION (CUT)	CHANNEL EXCAVATION	ROCK EXCAVATION IN CHANNEL	EARTH EXCAVATION ADJUST SHRINKAGE 25% EARTH	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) *	TOPSOIL EXCAVATIO AND PLACEMENT
STATION TO STATION		CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
STAGE 1								
<u>L 173 LT</u>								
1022+20.19	1027+00	684	0	0	513	688	-175	105
1027+00	1033+00	242	0	0	181	1672	-1491	78
1033+00	1039+00	3479	0	0	2609	338	2271	128
1039+00	1045+00	4624	0	0	3468	9	3459	188
1045+00	1051+00	2143	0	0	1607	132	1476	107
1051+00	1057+00	313	0	0	234	1441	-1206	198
1057+00	1063+00	50	0	0	38	3741	-3704	204
1063+00	1069+00	46	1366	0	1059	9598	-8539	603
1069+00	1072+00	0	2060	0	1545	6304	-4759	344
1072+00	1078+00	58	1330	0	1041	5529	-4488	603
CONTINENTAL DRIVE								
91+00	92+25	293	0	0	220	24	196	26
KIMBER DRIVE								
101+00	102+20	610	0	0	458	2	456	26
BURDEN ROAD								
216+00	217+66.08	791	0	0	593	25	568	63
MENARD'S SOUTH ENTR	ANCE							
131+00	132+00	120	0	0	90	43	47	18
OREST HILLS ROAD - RT								
376+10	380+00	0	0	0	0	0	0	0
380+00	385+50	704	0	0	528	16	512	33
385+50	391+50	4275	0	0	3206	158	3048	261
391+50	397+50	1662	0	0	1247	662	585	227
397+50	399+00	532	0	0	399	105	294	51
451+00	453+00	448	0	0	336	95	241	64
453+00	459+00	895	0	0	671	807	-136	131
459+00	465+00	1526	0	0	1145	265	880	199
465+00	469+48	241	0	0	181	36	145	57
PERRYVILLE ROAD - LT	0110	2-T1	0	0	101	50	175	5,
248+10.79	249+00	126	0	0	95	36	59	15
251+50	253+50	465	0	0	349	430	379	104
KRASS ROAD	233+30	400	U	U	549	430	3/9	104
	12 45 67	626		2	470	0		40
11+00	12.45.67	626	0	0	470	9	461	43
					22281			3876

FILE NAME =	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			SECTION	COUNTY TOTAL SHEET
\CADD SHEETS\Z00793CVR-SQ12.dgn		DRAWN - JAU	REVISED -		EARTHWORK - STAGE 1			129R	WINNEBAGO 968 51
THE UPCHURCH GROUP, INC.	PLOT SCALE = 2.0000 ' / IN.	CHECKED - RLH	REVISED -						CONTRACT NO. 64988
	PLOT DATE = 5/3/2013 3:03:54 PM	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT	