EARTHWORK - STAGE 4

		20200100	20300100	20300200			20400800	21101505
LOCATION		EARTH EXCAVATION (CUT)	CHANNEL EXCAVATION	ROCK EXCAVATION IN CHANNEL	EARTH EXCAVATION ADJUST SHRINKAGE 25% EARTH	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) *	TOPSOIL EXCAVATION AND PLACEMENT
STATION TO STATION		CU YD	CU YD	CUYD	CU YD	CU YD	CUYD	CU YD
STAGE 4								
IL 173 -LT ** QUAN	ITITY INCLUDED IN PR	RESTAGE						
MITCHELL ROAD								
232+00	234+00	402	0	0	302	2344	-2043	137
234+00	238+75	2243	0	0	1682	1261	421	351
					_			
TOTAL		2645	0	0	1984	3605	-1621	488

^{* 20400800} FURNISHED EXCAVATION

EARTHWORK - STAGE 5

		20200100	20300100	20300200			20400800	21101505
IOC	ATION	EARTH EXCAVATION (CUT)	CHANNEL EXCAVATION	ROCK EXCAVATION IN CHANNEL	EARTH EXCAVATION ADJUST SHRINKAGE 25% EARTH	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) *	TOPSOIL EXCAVATION
STATION TO STATION		CU YD	CU YD	CU YD	CU YD	CU YD	CUYD	CUYD
STAGE 5		99.15	00.15	33.12	00.15	00.15	33.12	55.15
IL 173 RT								
1078+00	1084+00	694	0	0	520	792	-272	305
1084+00	1090+00	537	0	0	403	951	-548	245
1090+00	1093+00	250	0	0	187	637	-449	110
1093+00	1099+00	768	0	0	576	1325	-749	280
1099+00	1105+00	160	0	0	120	1775	-1655	240
1105+00	1111+00	263	0	0	197 2078 -1881	-1881	303	
1111+00	1117+00	343	0	0	257	2182	-1925	312
1117+00	1123+00	528	0	0	396	4291	-3895	371
1123+00	1129+00	870	0	0	653	1997	-1344	352
1129+00	1135+00	1600	0	0	1200	1272	-72	370
1135+00	1141+00	1604	0	0	1203	658	545	280
1141+00	1142+88.00	311	0	0	233	364	-131	88
1142+88.00	1147+00	780	0	0	585	582	3	153
1147+00	1152+00	886	0	0	665	399	266	17
	TOTAL	9594	0	0	7196	19302	-12107	3426

^{* 20400800} FURNISHED EXCAVATION

FILE NAME =		USER NAME = Elgin 110	DESIGNED - MJS	REVISED -
	\CADD SHEETS\Z00793CVR-SQ12.dgn		DRAWN - JAU	REVISED -
		PLOT SCALE = 2,0000 '/ IN.	CHECKED - RLH	REVISED -
THE	THE UPCHURCH GROUP, INC.	PLOT DATE = 5/3/2013 3:05:01 PM	DATE -	REVISED -

STATE	0F	ILLINOIS
DEPARTMENT O	FT	TRANSPORTATION

SCALE:

SCHEDULE OF QUANTITIES EARTHWORK — STAGES 4 & 5					F.A.P. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEE NO.	
					303	129R		WINNEBAGO	968	53	
LAITHWOIR - STAGES 7 & 3									CONTRACT	NO. 6	4988
	SHEET NO.	OF	SHEETS	STA.	TO STA.		ILLINOIS F	FED. AI	D PROJECT		

^{**} COMPLETE BULK EARTHWORK IN PRESTAGE AND THE REMAINDER IN STAGE 4