

TEMPORARY EROSION CONTROL

LOCATION		25000350	25100115	28000250	28000305	28000400	28000500	28000510	
		SEEDING, CLASS 7	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	INLET FILTERS	
STATION TO STATION	OFFSET	ACRE	ACRE	POUND	FOOT	FOOT	EACH	EACH	
IL 173									
1022+20.19	1027+00	RT	0.12	0.12	125.6	20.0	309.0	2	4
1022+20.19	1027+00	LT			63.1		487.5	4	6
1027+00	10333+00	RT	0.12	0.12	131.9		471.2	8	8
1027+00	1033+00	LT			48.8		513.0	4	4
1033+00	1039+00	RT	0.12	0.12	110.1	10.0	221.1	6	5
1033+00	1039+00	LT			80.1		150.0	6	6
1039+00	1045+00	RT	0.25	0.25	123.4	40.0		6	5
1039+00	1045+00	LT			117.5	30.0		6	5
1045+00	1051+00	RT	0.17	0.17	79.6		338.6	9	9
1045+00	1051+00	LT			66.8			4	4
1051+00	1057+00	RT	0.28	0.28	143.3	50.0		7	6
1051+00	1057+00	LT			123.9		809.6	6	6
1057+00	1063+00	RT	0.15	0.15	145.9	20.0	113.7	7	7
1057+00	1063+00	LT			125.4		586.0	6	4
1063+00	1069+00	RT	0.02	0.02	310.0	30.0	29.9	6	5
1063+00	1069+00	LT			378.1	9.0	86.8	4	4
1069+00	1072+00	RT			140.0	20.0		2	2
1069+00	1072+00	LT			215.7			4	4
1072+00	1078+00	RT			173.3	62.0		8	5
1072+00	1078+00	LT			372.8			4	4
1078+00	1084+00	RT			203.3	76.0		9	6
1078+00	1084+00	LT	0.52	0.52	256.7		421.8	4	4
1084+00	1090+00	RT			160.0	115.0		4	4
1084+00	1090+00	LT	0.88	0.88	200.0		526.4	7	4
1090+00	1093+00	RT			93.3	59.0		4	2
1090+00	1093+00	LT	0.48	0.48	116.7		300.9	2	2
1093+00	1099+00	RT			203.3	108.0		6	4
1093+00	1099+00	LT	0.96	0.96	240.0		625.1	4	3
1099+00	1105+00	RT			186.7	117.0		4	2
1099+00	1105+00	LT	0.96	0.96	220.0		596.6	2	2
1105+00	1111+00	RT			210.0	93.0		8	4
1105+00	1111+00	LT	0.96	0.96	206.7		611.0	5	4
1111+00	1117+00	RT			216.7	75.0		5	3
1111+00	1117+00	LT	0.96	0.96	383.3		146.0	4	2
1117+00	1123+00	RT			280.0	167.0		9	4
1117+00	1123+00	LT	0.96	0.96	716.7			4	4
1123+00	1129+00	RT			236.7	160.0		6	4
1123+00	1129+00	LT	0.96	0.96	486.7			6	4
1129+00	1135+00	RT			270.0	182.0		7	3
1129+00	1135+00	LT	0.96	0.96	486.7			3	3

LOCATION		25000350	25100115	28000250	28000305	28000400	28000500	28000510	
		SEEDING, CLASS 7	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	INLET FILTERS	
STATION TO STATION	OFFSET	ACRE	ACRE	POUND	FOOT	FOOT	EACH	EACH	
1135+00	1141+00	RT			193.3	216.0		7	5
1135+00	1141+00	LT	0.96	0.96	483.3		76.0	6	4
1141+00	1147+00	RT			150.0	98.0		7	4
1141+00	1147+00	LT	0.27	0.27	60.0		184.0	3	1
1147+00	1152+00	RT			10.0			3	3
1147+00	1152+00	LT						1	
CONTINENTAL DRIVE									
87+75	92+58	RT			20.0			1	2
87+75	92+25	LT			26.7			1	2
KIMBER DRIVE									
97+80	102+20	RT			43.3				
97+80	102+20	LT			26.7		125.2		
BURDEN ROAD									
213+00	217+66	RT			20.0			2	
213+00	217+66	LT			20.0			1	
FOREST HILLS ROAD									
374+00	380+00	RT							
374+00	380+00	LT			40.8				
380+00	385+50	RT			20.4				
380+00	385+50	LT			106.9		901.6		
385+50	391+50	RT			163.0	18.0		4	2
385+50	391+50	LT			52.3		640.4		
391+50	397+50	RT			138.4			10	5
391+50	397+50	LT			125.6		734.7	6	6
397+50	453+00	RT			71.5	9.0		6	5
397+50	453+00	LT			42.4		156.0	4	4
453+00	459+00	RT			81.5	36.0		6	4
453+00	459+00	LT			118.6		280.2	3	3
459+00	465+00	RT			122.3	9.0		7	5
459+00	465+00	LT			125.7	54.0		3	3
465+00	471+00	RT			35.7			2	
465+00	471+00	LT			93.3	9.0	311.5		
SUBTOTAL		11.1	11.1	10840.5	1892.0	10753.8	295	229	

FILE NAME = ...\\CADD SHEETS\Z00793CVR-S011.dgn	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -
		DRAWN - JAU	REVISED -
		CHECKED - RLH	REVISED -
		DATE - APRIL 30, 2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
TEMPORARY EROSION CONTROL**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	55
			CONTRACT NO. 64988	
ILLINOIS FED. AID PROJECT				

THE UPCHURCH GROUP, INC.