

TEMPORARY EROSION CONTROL

LOCATION		25000350	25100115	28000250	28000305	28000400	28000500	28000510
		SEEDING, CLASS 7	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	INLET FILTERS
STATION TO STATION	OFFSET	ACRE	ACRE	POUND	FOOT	FOOT	EACH	EACH
PERRYVILLE ROAD								
248+10	253+50	RT		86.7	15.0		1	1
248+10	253+50	LT		80.0				
MITCHELL ROAD								
230+51.49	234+00	RT		113.3	36.0		1	1
230+51.49	234+00	LT		90.0	36.0	288.5	1	1
234+00	238+75	RT		146.7	45.0		1	
234+00	238+75	LT		103.3	27.0	285.9	2	
CONTRACTORS DRIVE / KRASSE DRIVE								
6+35	9+00	RT		14.9				
6+35	9+00	LT		11.6				
9+00	12+45	RT		35.9				
9+00	12+45	LT		11.1				
SUBTOTAL		0.0	0.0	693.5	159.0	574.4	6	3
TOTAL		11.25	11.25	11534	2051	11329	301	232

FILE NAME = ...\\CADD SHEETS\Z00793CVR-S011.dgn	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -
		DRAWN - JAU	REVISED -
		CHECKED - RLH	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES TEMPORARY EROSION CONTROL			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	56
CONTRACT NO. 64988			ILLINOIS FED. AID PROJECT	

THE UPCHURCH GROUP, INC.