TEMPORARY ACCESS TO SIDE ROADS AND ENTRANCES

	LOCATION TRAFFIC CONTROL TREATMENT TEMPORARY ACCESS CONDITIONS DURING CONSTRUCTION		DIMENSIONS		35101400 AGGREGATE BASE COURSE TYPE B	40201000 AGGREGATE FOR TEMPORARY ACCESS	40600200 BITUMINOUS MATERIALS (PRIME COAT)	40800050 INCIDENTAL HMA SURFACING **	X4421000 PARTIAL DEPTH PATCHING
LOCATION									
			LENGTH (FT)	WIDTH (FT)	TON	TON	TON	TON	TON
PRESTAGE 1									
KIMBER DRIVE (SOUTH LEG) - Sta. 1036+79 RT	Close	Close for 5 Week Days	110	32					65.7
FOREST HILLS LODGE ENTRANCE - Sta. 1047+30 RT	Close	Close for 3 Week Days - Speedway North Entrance Open	50	28	156		0.22	17.4	
SPEEDWAY NORTH ENTRANCE - Sta. 1050+50 RT	Close	Close for 3 Week Days - Forest Hills Lodge Entrance Open	35	20	78		0.11	8.7	
PARK DISTRICT ENTRANCE - Sta. 378+82 LT	Maintain 1 Lane	Reduce to 1 I ane for Max. of 2 weeks	22	26			0.09	14.2	
TORQUE ROAD (WEST LEG) - Sta. 383+30 LT	Maintain 1 Lane	Reduce to 1 I ane for Max of 2 Weeks							
CONTRACTORS DRIVE - Sta. 389+20 LT	Maintain 1 Lane	Existing East Speedway Entrance open	10	26			0.1	3.3	
SPEEDWAY ENTRANCE - Sta. 389+80 LT	Close	Close for 5 Weekdays - Contractors Drive Open							
SPEEDWAY EAST ENTRANCE - Sta. 393+00 LT	Close	Close for 3 Weekdays - Speedway North Entrance Open	30	20			0.3	33.6	
MENARDS EAST ENTRANCE - Sta. 453+76 LT	Close	Close for 3 Week Days - Menards South Entrance and Burden Road Open	40	16					12.0
ENTRANCE OFF FOREST HILLS - Sta. 464+28 LT	Close	Close for 3 Weekdays	40	24		73			
MITCHELL ROAD - Sta. 113+28	Close	Detour Route							
PRESTAGE 1A									
CONTINENTAL DRIVE (NORTH LEG) - Sta. 1028+53 LT	Close	Close for 7 Days	250	24					112.0
STAGE 1, 1A and 1B - IL 173									
KIMBER DRIVE (NORTH LEG) - Sta. 1036+79 LT	Close	Continental and Burden open	40	26	75		0.17	12.9	
BURDEN ROAD (NORTH LEG) - Sta. 1046+10 LT	Maintain 1 Iane North (in)	Continental and Kimber open	20	26	37		0.08	6.5	
MENARDS SOUTH ENTRANCE - Sta. 1053+70 LT	Maintain 1 Iane North (in)	Burden and East Entrance off Forest Hills Road Open -	11	36	34		0.02	5.0	
WENANDS SOOTH ENTHANCE Sta. 1055170 ET	Wantan Francisch (III)	Temp. Raise IL 173 - See Roadway Profile	200	36			0.3	322.6	
PERRYVILLE ROAD - Sta. 1074+34	Staged Construction	See Temporary Ramp Schedule							
PUMP STATION ENTRANCE - Sta. 1087+42 LT	Close	Co-ordinate Closure with VMP	75	13		189			
MITCHELL ROAD - Sta. 1113+28	Close	Detour Route							
STAGE 1C- IL 173									
CONTINENTAL DRIVE (NORTH LEG) - Sta. 1028+53 LT	Gap and Close prior to switching to Stage 2 - Close 11 days prior to closing Forest Hills Road North Leg	Kimber and Burden open							
FOREST HILLS ROAD - Sta. 1059+39	Staged Construction	Close North Leg Forest Hills Road for 10 Days - South Leg of Forest Hills Road Open - Burden Road Open							
PERRYVILLE ROAD - Sta. 1074+34	Staged Construction	See Temporary Ramp Schedule							
MITCHELL ROAD - Sta. 1113+28	Close	Detour Route							
		SUBTOTAL			380	262	1.39	424.2	189.7

THE	UPCHURCH	GROUP.	INC
\CADE	SHEETS\ZØØ793	CVR-SQ18.dg	n
FILE N	4ME =		

USER NAME = Elgin 110	DESIGNED	-	MJS	REVISED -
	DRAWN	-	JAU	REVISED -
PLOT SCALE = 2,0000 '/ IN.	CHECKED	-	RLH	REVISED -
PLOT DATE = 5/3/2013 3:11:31 PM	DATE	-	APRIL 30, 2013	REVISED -

SCHEDULE OF QUANTITIES								
	TEMPORARY	ACCESS	TO SIDE	ROADS AND	ENTRANCES			
SCALE:	SHEET	NO. OF	SHEETS	STA.	TO STA.			

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHI				
303	129R	WINNEBAGO	968	6				
		CONTRACT	Γ NO. 6	49				
ILLINOIS FED. AID PROJECT								