DRAINAGE REMOVAL SCHEDULE

PAY ITEM NUMBER		50105220	55100500	55100700	55100900	55101100	5510200	60500040	60500050	60500060	X0322936
STATION	OFFSET	PIPE CULVERT REMOVAL	STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 21"	STORM SEWER REMOVAL 24"	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	REMOVE EXISTING FLARED END SECTION
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH
IL 173	'	1	•		!				1		
1024+53.62	33.35' RT									1	
1024+55	LT		9.00								
1024+55.64	46.17' LT							1			
1026+44.82	26.27' RT									1	
1026+45.88	21.40' LT						11.00			1	
1026+46	LT			11.00							
1027+29	LT				125.00						
1027+68.85	24.12' LT							1			
1028+42	RT	273.00									
1029+48.61	23.69' LT							1			
1028+60	LT	180.00									
1029+61.54	LT	30.00									
1035+62.71	35.65' RT								1		
1036+50	RT	269.00									
1036+90	LT	221.00									
1037+80.80	22.90' RT							1			
1037+84.74	40.55' LT							1			
1043+53	RT	88.00									
1047+27	RT	64.00									
1050+51	RT	56.00									
1053+75	LT	113.00									
1064+08	RT					14.00					
1064+10	84.7' RT							1			
1065+15	RT						210.00				
1066+19	RT					5.10					
1066+19.30	88.1' RT							1			
1066+20	96.2' RT							1			
1066+37	RT					37.90					
1066+67	RT			95.40							
1067+46	RT	110.00									
1073+15	CROSS	134.30									
1075+45	CROSS	139.50									
1075+50	CROSS	139.50									
1078+20	CROSS	110.80									
1087+39	LT	29.60									
1130+87	RT	63.33									
1142+85	0.0'										1
1142+85	18.8' RT										1
1148+00	57.2' RT		143.00								
1152+32.66	6.79' RT							1			
1153+31	RT			197.00				-			
	SUBTOTAL	. 2021.03	152	303.4	125	57	221.00	9.00	1.00	3.00	2.00

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

FILE NAME =

...\CADD SHEETS\ZØØ793CVR-SQØ5.dgn

USER NAME = Elgin 110

THE UPCHURCH GROUP, INC. PLOT DATE = 5/3/2013 4:18:56 PM

DESIGNED - MJS

DRAWN - JAU

CHECKED - RLH

DATE - APRIL 30, 2013

REVISED

REVISED

REVISED

REVISED

COUNTY TOTAL SHEET NO.

129R WINNEBAGO 968 69

CONTRACT NO. 64988

ILLINOIS FED. AID PROJECT

F.A.P. RTE. 303

TO STA.

SCHEDULE OF QUANTITIES

DRAINAGE REMOVAL SCHEDULE

SHEET NO. OF SHEETS STA.

SCALE:

SECTION