

DRAINAGE REMOVAL SCHEDULE

PAY ITEM NUMBER		50105220	55100500	55100700	55100900	55101100	5510200	60500040	60500050	60500060	X0322936
STATION	OFFSET	PIPE CULVERT REMOVAL	STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 21"	STORM SEWER REMOVAL 24"	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	REMOVE EXISTING FLARED END SECTION
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH
FOREST HILLS ROAD											
390+16.59	51.31' RT									1	
390+48	RT	62.30									
390+78.75	54.97' RT									1	
390+86	RT	20.40									
395+07	RT	17.30									
396+65	RT	46.40									
453+70	RT	32.70									
455+52	RT	56.60									
454+51.37	CROSS	83.00									
454+63.06	CROSS	82.80									
454+75.15	CROSS	82.90									
458+18	LT	39.80									
460+19	CROSS	51.20									
464+34	RT	95.80									
390+92.40	73.33' RT							1			
455+95.06	RT	20.90									
465+98.50	32.9' LT										1
PERRYVILLE ROAD											
252+00	8.0' RT									1	
252+00	RT	52.00									
MITCHELL ROAD											
232+00	CROSS	48.50									
232+10.26	CROSS	48.50									
234+70	LT	124.80									
236+77	LT	30.30									
OSF ENTRANCE											
38+53.90	33.5' LT							1			
38+59.50	26.8' LT		14.00								
38+65.57	18.2' LT									1	
36+66	CROSS		34.00								
38+67.75	15.3' RT									1	
SUBTOTAL		996.20	48.00	0	0	0	0	2	0	5	1
TOTAL		3017.23	200.00	303.40	125.00	57.00	221.00	11	1	8	3
ROUNDED TOTAL		3018	200	304	125	57	221	11	1	8	3

FILE NAME = ...\\CADD SHEETS\200793CVR-S005.dgn	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -
THE UPCHURCH GROUP, INC.	PLOT SCALE = 2.0000' / IN.	DRAWN - JAU	REVISED -
	PLOT DATE = 5/3/2013 4:19:09 PM	CHECKED - RLH	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES DRAINAGE REMOVAL SCHEDULE			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	70
			CONTRACT NO. 64988	
ILLINOIS FED. AID PROJECT				