## **DRAINAGE PIPE SCHEDULE**

PAY ITEM NUMBER		NUMBER 20800150		550A0050	550A0340	0A0340 Z0056608 550A0070 550A0360 5	550A0380	550A0380 Z0056612	550A0410	550A0410 550A4900	550A0430	550A0450	Z0056622	550A0470	550A0480	60107600				
	I				12"	•	1	5"	1	8"	2	24"	30"	3	36"	42"	48"			
				CLA	SS A	WMREQ	CLASS A		CLASS A	WM REQ	CLASS A	CLASS A	CLASS A	CLASS A		CLASS A  TYPE 2	CLASS A  TYPE 2	PIPE UNDER DRAINS 4"	<b>I</b>	
			JRE TRENCH BACKFILL	TYPE 1	TYPE 2	TYPE 2	TYPE 1	TYPE 2	TYPE 2	TYPE 2	TYPE 2	TYPE 2 EQRS	TYPE 2	TYPE 2	TYPE 2					
SHEET	то	FROM	CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	то	FROM
D4	132	131	9.3					32.4											132	131
D4	133	132	17.7					62.7											133	132
D4	131																	49.0	131	
D4	131	138	27.6		161.2														131	138
D4	139	138																89.8	139	138
D4	142	137	0.7				83.1											94.7	142	137
D4	133	141	258.2													225.1			133	141
D4	140	139	44.0					61.9											140	139
D4	139	144	0.0															130.6	139	144
D4	141	140	27.5					35.3											141	140
D4	140	145	0.0															132.0	140	145
D4	141	142	0.0				7.9												141	142
D4	141	146	140.7													128.7		130.0	141	146
D5	144	143	0.0				6.5												144	143
D5	145	144	14.6					61.8											145	144
D5	144	147	0.0					02.0										210.2	144	147
D5	146	145	9.9					32.2											146	145
D5	145	148	0.0					52.2										214.3	145	148
D5	146	149	217.3													209.0		209.9	146	149
D5	148	147	11.3					47.9								203.0		203.3	148	147
D5	147	153	0.0					47.3										185.0	147	153
D5	149	148	9.8					37.6										165.0	149	148
 D5	148	151	0.0					37.0										102.4	148	151
D5	149	150	0.0				9.0											102.4	149	150
D5	149	155	171.5				5.0									184.0		184.9	149	155
D5	153	152	0.0	10.3												104.0		104.9	153	152
	154	151	17.5	10.5				82.1										81.9	154	151
D5 D5	154	153	11.2					31.7								+		01.3	154	153
D5	153	156	0.0					31./								+		162.8	153	156
D5	155	154	19.6					49.3										102.0	155	154
		157						49.5								+		167.0		
D5	154		0.0													164.0		167.0	154	157
D5	155	158	152.9					42.0								164.0		164.8	155	158
D6	157	156	9.9					42.0											157	156
D6	158	157	14.1					49.8						100.0		-		100.0	158	157
D6	158	162	182.0					60.5						198.8				199.9	158	162
D6	161	160	14.3					60.5								+		462.0	161	160
D6	160	164	0.0					212										163.9	160	164
D6	162	161	9.7					34.3											162	161
	Sl	UBTOTAL	1391.4	10.3	161.2	0.0	106.5	721.5	0.0	0.0	0.0	0.0	0.0	198.8	0.0	910.8	0.0	2673.1		

<sup>\*</sup> SEE S.P. STORM SEWER, RUBBER GASKET

FILE NAME =	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -
\CADD SHEETS\ZØØ793CVR-SQØ2.dgn		DRAWN - JAU	REVISED -
	PLOT SCALE = 2.00000 '/ IN.	CHECKED - RLH	REVISED -
THE UPCHURCH GROUP, INC.	PLOT DATE = 5/3/2013 4:20:31 PM	DATE -	REVISED -

STATI	E OF	: ILLINOIS
DEPARTMENT	OF	TRANSPORTATION

SCALE:

SCHEDULE OF QUANTITIES							SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DE	ΔΙΝΔ	E PIPE S	CHEDIII	303	129R	WINNEBAGO	968	72	
DRAINAGE PIPE SCHEDULE								CONTRACT	NO. 6	54988
	SHEET NO.	0F	SHEETS	STA.	TO STA.		TILINOIS FED AT	ID PROJECT		