## **DRAINAGE PIPE SCHEDULE**

PAYI	ITEM NU	JMBER	20800150	550A0050	550A0340	Z0056608	550A0070	550A0360	550A0380	Z0056612	550A0410	550A4900	550A0430	550A0450	Z0056622	550A0470	550A0480	60107600		
					12"	•	1	15"	1	.8"	2	24"	30"	3	6"	42"	48"			
	STRUCTURE			CLA	SS A	WM REQ		ASS A	CLASS A	WMREQ	CLASS A	CLASS A	CLASS A	CLASS A		CLASS A	CLASS A	PIPE UNDER	STRUCT	URE
			TRENCH BACKFILL	TYPE 1	TYPE 2	TYPE 2	TYPE 1	TYPE 2	TYPE 2	TYPE 2	TYPE 2	TYPE 2 EQRS	TYPE 2	DRAINS 4"						
SHEET	ТО	FROM	CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	то	FRON								
D11	333	334	0.0					23.3											333	334
D11	334	335	17.8					62.8											334	335
D11	334	338	0.0															113.0	334	338
D11	335	336	12.5					52.7											335	336
D11	336	340	0.0															115.1	336	340
D11	337	338	0.0					23.3											337	338
D11	338	339	16.0					61.8											338	339
D11	338	342	0.0															156.9	338	342
D11	339	335	0.0															115.0	339	335
D11	339	340	9.5					40.3											339	340
D11	339	343	0.0															159.3	339	343
D11	340	344	0.0															157.1	340	344
D12	341	342	0.0					21.3											341	342
D12	342	343	14.6					61.8											342	343
D12	342	346	0.0															147.5	342	346
D12	343	344	6.9					32.2											343	344
D12	343	347	0.0															149.8	343	347
D12	344	348	0.0															147.9	344	348
D12	345	346	0.0					20.9											345	346
D12	346	347	13.1					55.6											346	347
D12	346	350	0.0															136.9	346	350
D12	347	348	7.5					35.3											347	348
D12	348	352	0.0															136.9	348	352
D12	349	350	0.0					22.3											349	350
D12	350	351	10.6					41.0											350	351
D12	350	354	0.0															142.9	350	354
D12	351	352	9.7					41.0											351	352
D12	352	356	0.0															142.9	352	356
D12	353	354	0.0					23.3											353	354
D12	354	355	10.6					41.0											354	355
D12	354	358	0.0															124.9	354	358
D12	355	356	9.7					41.0											355	356
D12	356	360	0.0															124.9	356	360
D13	357	358	0.0					22.3											357	358
D13	358	359	10.2					39.1											358	359
D13	358	362	0.0															136.8	358	362
D13	359	360	10.1					42.9											359	360
D13	360	364	0.0															136.9	360	364
	S	SUBTOTAL	158.9	0.0	0.0	0.0	0.0	805.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2344.7		

FILE NAME =

	USER NAME = Elgin IIV	DESIGNED - MJS	KEVISED -
		DRAWN - JAU	REVISED -
	PLOT SCALE = 2,0000 '/ IN.	CHECKED - RLH	REVISED -
;.	PLOT DATE = 5/3/2013 4:21:25 PM	DATE -	REVISED -

## STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

	SC	F.A.P. RTE.	SECTION	COUNTY TO							
	DR	303	129R	WINNEBAGO	96						
	, Dn			CONTRACT	ΓNO						
SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT					