DRAINAGE PIPE SCHEDULE

PAY ITEM NUMBER		JMBER	20800150	550A0050	550A0340	Z0056608	550A0070	550A0360	550A0380	Z0056612	550A0410	550A4900	550A0430	550A0450	Z0056622	550A0470	550A0480	60107600		
				12"	•	1	5"	1	.8"	2	24"	30"	3	6"	42"	48"				
			CLASS A			CLASS A	CLASS A	WMREQ	CLASS A	CLASS A	CLASS A	CLASS A		CLASS A	CLASS A	PIPE UNDER	STRUCTURE			
	STRU	JCTURE	TRENCH BACKFILL	TYPE 1	TYPE 2	TYPE 2	TYPE 1	TYPE 2	TYPE 2	TYPE 2	TYPE 2	TYPE 2 EQRS	TYPE 2	TYPE 2	TYPE 2	TYPE 2	TYPE 2	DRAINS 4"		
SHEET	то	FROM	CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	TO	FROM								
D18	428	423	36.1					139.2										143.7	428	423
D18	427	424	66.6		100.2														427	424
D18	901	426	0.0															153.0	901	426
D18	425	426	0.0					36.3											425	426
D18	426	427	37.7					53.0											426	427
D18	426	430	0.0															215.1	426	430
D18	427	428	29.2					41.0											427	428
D18	428	432	0.0															221.6	428	432
D19	429	430	0.0					21.8											429	430
D19	430	431	12.7					48.8											430	431
D19	430	434	0.0															110.5	430	434
D19	431	432	9.7					41.1											431	432
D19	432	436	0.0															111.4	432	436
D19	433	434	0.0					23.8											433	434
D19	434	435	10.6					41.0											434	435
D19	434	438	0.0															178.5	434	438
D19	435	436	9.7					41.0											435	436
D19	436	440	0.0															183.3	436	440
D19	437	438	0.0					22.3											437	438
D19	438	439	10.6					41.0											438	439
D19	438	442	0.0															180.5	438	442
D19	439	440	9.7					41.0											439	440
D19	440	444	0.0															181.2	440	444
D19	441	442	0.0					25.3											441	442
D19	442	443	10.6					41.0											442	443
D19	442	446	0.0															163.9	442	446
D19	443	444	9.7					41.0											443	444
D19	444	448	0.0															163.6	444	448
D20	445	446	0.0					22.3											445	446
D20	446	447	10.0					35.5											446	447
D20	446	450	0.0															87.4	446	450
D20	447	448	11.0					46.5											447	448
D20	448	451	18.0					108.0											448	451
D20	448	456	0.0															325.9	448	456
D20	449	450	0.0					20.0											449	450
D20	450	454	0.0															235.6	450	454
D20	455	452	18.0		76.3														455	452
D20	453	454	0.0					21.3											453	454
	S	UBTOTAL	310.1	0.0	176.5	0.0	0.0	952.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2655.2		

^{*} SEE S.P. STORM SEWER, RUBBER GASKET

	SHEETS\ZØØ793	
THE	UPCHURCH	GROUP, INC.

FILE NAME =

	USER NAME = Elgin 110	DESIGNED - MJS	KENIZED -
		DRAWN - JAU	REVISED -
	PLOT SCALE = 2.00000 '/ IN.	CHECKED - RLH	REVISED -
•	PLOT DATE = 5/3/2013 4:23:43 PM	DATE -	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE:

S	CHEDU	LE OF QU	ANTITIES		F.A.P. RTE.	SECT
DI	ΑΙΝΔ	F PIPE S	CHEDULE		303	12
	miim	JE 1 11 E C	OHLDOLL			
SHEET NO.	0F	SHEETS	STA.	TO STA.		

F.A.P. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHI
303	129R		WINNEBAG0	968	7
			CONTRACT	NO. 6	49
	ILLINOIS	FED. AI	D PROJECT		