

DRAINAGE STRUCTURE ADJUSTMENT SCHEDULE

SHEET	DESC.	STATION	OFFSET	60255500	60260100	STRUCTURE TYPE	EX RIM ELEV	PROP RIM ELEV	PROP INVERT	COMMENTS
				MANHOLES TO BE ADJUSTED	INLETS TO BE ADJUSTED					
				EACH	EACH					
D1	A11	1015+97.32	6.79' RT		1	INLET TYPE B	737.28	737.28	N/A	REPLACE EX F&G WITH TYPE 11 F&G
D1	A12	1020+72.50	8.0' RT	1		MANHOLE TYPE 4	738.59	738.59	N/A	REPLACE EX F&G WITH TYPE 11 F&G
D2	A1	1022+62.43	40.00' RT		1	INLET NO. 5 SPL	738.67	738.80	N/A	
D2	A2	1022+64.49	52.00' LT		1	INLET NO. 7 SPL	738.40	738.51	N/A	
D2	A15	1022+64.49	34.0' LT	1		MANHOLE	738.81	738.93		
D2	A16	1024+55.14	34.87' LT	1		MANHOLE	738.48	739.41	± N 732.30	CORE EX. MANHOLE FOR 12" RCP
D2	A17	1026+46.40	34.0' LT	1		MANHOLE	736.96	740.03	± E 730.45	CORE EX. MANHOLE FOR 48" RCP
D3	A3	91+48.16	24.57' LT		1	INLET NO. 3 SPL	736.64	737.39	N/A	CORE EX. INLET FOR 12" RCP
D3	A4	91+48.03	29.30' RT		1	INLET NO. 3 SPL	736.70	737.29	MATCH EX	MOVE W / 5' NEW PIPE, CORE EX. INLET FOR 12" RCP
D7	A5	131+82.09	13.00' LT		1	INLET NO. 3 SPL	752.37	752.59	N/A	
D7	A6	131+81.60	13.00' RT		1	INLET NO. 3 SPL	752.33	752.59	N/A	
D24	A8	1147+33.78	52.00' RT		1	INLET NO. 5 SPL	857.67	857.30	N/A	MOVE W / 1.4' NEW PIPE
D24	A9	1149+60.79	52.00' RT		1	INLET NO. 5 SPL	861.44	861.50	N/A	CORE EX. INLET FOR 12" RCP
D24	A10	1150+85.66	52.00' RT		1	INLET NO. 5 SPL	863.72	863.80	N/A	CORE EX. INLET FOR 12" RCP
D30	A13	460+54.90	43.74' RT		1	PRCFES			± 760.36	REMOVE 2' 12" RCP REPLACE W/EX PRCFES (EX INV. 760.20)
D30	A14	464+48.02	35.65' RT	1		MANHOLE	758.76	758.87	N/A	
TOTAL				5	11					