GROUND MOUNTED SIGN SCHEDULE

					72000100	72000200	72800100	73000100	
SIGN NUMBER	LOCAT	ION	SIGN WIDTH	SIGN HEIGHT	SIGN PANEL, TYPE 1	SIGN PANEL, TYPE 2	TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT (4" X 6")	COMMENTS
	STATION	OFFSET	FOOT	FOOT	SQ FT	SQ FT	FOOT	FOOT	
R6-1R	1051+02	RT	3.0	1.0	3.0				AP SHEETING - WHITE
W3-3	1052+00	LT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Burden Road	1052+00	LT	4.0	1.5	6.0				AZ SHEETING - YELLOW
W3-3	1052+90	RT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Forest Hills Road	1052+90	RT	4.0	1.5	6.0				AZ SHEETING - YELLOW
R6-1R	1053+20	LT	3.0	1.0	3.0		12.0		AP SHEETING - WHITE
R1-1	1053+40	LT	2.5	2.5	5.18		15.5		ZZ SHEETING - RED
R6-2R	1053+40	LT	1.5	2.0	3.0				AP SHEETING - WHITE
R3-2	1053+73	LT	2.5	2.5	6.25		13.5		AP SHEETING - WHITE
R2-1	1057+50	RT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R4-7	1058+28	RT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1059+23	RT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1059+50	LT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1060+48	LT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R2-1	1061+45	LT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
W3-3	1066+00	LT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Forest Hills Road	1066+00	LT	4.0	1.5	6.0				AZ SHEETING - YELLOW
R3-2	1067+50	RT	2.5	2.5	6.25		13.5		AP SHEETING - WHITE
R6-1R	1068+01	LT	3.0	1.0	3.0		12.0		AP SHEETING - WHITE
R1-1	1067+81	RT	2.5	2.5	5.18		15.5		ZZ SHEETING - RED
R6-2R	1067+81	RT	1.5	2.0	3.0				AP SHEETING - WHITE
W3-3	1069+50	RT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Perryville Road	1069+50	RT	4.0	1.5	6.0				AZ SHEETING - YELLOW
R2-1	1071+10	LT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R4-7	1073+25	LT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1074+22	RT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1074+47	LT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1075+42	RT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R2-1	1079+00	RT	3.0	4.0	0.0	12.0	10.0	20.0	AP SHEETING - WHITE
		1				1.2.0			
W3-3	1081+70	LT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Perryville Road	1081+70	LT	4.0	1.5	6.0				AZ SHEETING - YELLOW
R2-1	1085+00	LT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R2-1	1090+00	RT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R2-1	1097+00	LT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R2-1	1097+00	RT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
				SUBTOTAL	107.9	176.0	190.0	260.0	
				JUDIUIAL	107.8	170.0	190.0	200.0	

...\CADD SHEETS\Z00793CVR-S020.dgn

THE UPCHURCH GROUP, INC.

FILE NAME =

	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -
		DRAWN - JAU	REVISED -
	PLOT SCALE = 2.0000 '/ IN.	CHECKED - RLH	REVISED -
; .	PLOT DATE = 5/3/2013 4:33:18 PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE:

SCHEDULE OF QUANTITIES					F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
GROUND MOUNTED SIGN SCHEDULE						303	129R	WINNEBAGO	968	100	
GHOOME MOONIED SIGH SUILDULL							CONTRACT	T NO. 6	4988		
	SHEET NO.	OF	SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT				