

SANITARY SEWER PIPE SCHEDULE

(SEE RRWRD SANITARY SEWER PLANS FOR MANHOLE LOCATIONS)

| STRUCTURE | | X0327420 | X0327421 | X0327422 | X0840000 | X0323814 | X0324970 | Z0068200 | COMMENTS |
|--------------------------|---------|----------------------------------|-----------------------------------|---|----------------------------|-----------------------------|--------------------------------|-------------------|---|
| | | SANITARY SEWER, DUCTILE IRON, 8" | SANITARY SEWER, DUCTILE IRON, 18" | SANITARY SEWER, PVC (D3034) SDR 35, 18" | SANITARY SEWER REMOVAL, 8" | SANITARY SEWER REMOVAL, 18" | SANITARY SEWER PIPE PROTECTION | STEEL CASINGS 30" | |
| TO | FROM | FOOT | FOOT | FOOT | FOOT | FOOT | EACH | FOOT | |
| IL 173 | | | | | | | | | |
| 179-002 | MH 3 | | 294.3 | | | | | | |
| 179-003 | MH 3 | | | | 15.0 | | | | Remove 15' Ex. Steel Casing |
| MH 3 | 179-004 | | | 485.3 | | | | | |
| MH3 | 179-004 | | | | | | | 200 | See Specification "Steel Casings 30" for Sanitary Sewers" |
| 179-201 | MH 4 | | | | 20.0 | | | | |
| 179-200 | 179-201 | | | | 34.4 | | | | |
| 179-200 | MH 4 | 54.0 | | | | | | | |
| 179-018 | 179-019 | | 252.4 | | | 252.4 | 1 | | |
| 179-076 | MH 5 | | | 214.0 | | | | | |
| MH 5 | 179-022 | | | 535.0 | | | | | |
| FOREST HILLS ROAD | | | | | | | | | |
| MH 1 | MH 2 | | | 158.4 | | | | | |
| TOTALS | | 54 | 547 | 1393 | 70 | 253 | 1 | 200 | |

GABIONS

| | | | 28400100 |
|--------------|--------|---------|-----------|
| STATION | OFFSET | RT / LT | GABIONS |
| | | | CU YD |
| 1115+00 | 133" | LT | 26 |
| TOTAL | | | 26 |

PROTECTIVE COAT

| | | 42001300 |
|---|--|-----------------|
| | | PROTECTIVE COAT |
| | | SQ YD |
| | | 7000 |
| TOTAL | | 7000 |
| LOCATIONS AND EXTENT OF PROTECTIVE COAT TO BE DETERMINED BY THE RESIDENT ENGINEER | | |

FILLING MANHOLES

| | | | 60500105 |
|--------------------------|--------|---------|------------------|
| STATION | OFFSET | RT / LT | FILLING MANHOLES |
| | | | EACH |
| FOREST HILLS ROAD | | | |
| 396+67.95 | 115.7' | RT | 1 |
| TOTAL | | | 1 |

WOVEN WIRE FENCE, 4"

| | | 66500105 |
|---------------------------------------|--|----------------------|
| STATION TO STATION | | WOVEN WIRE FENCE, 4" |
| | | FOOT |
| IL 173 | | |
| 1075+82, 175' RT to 1075+82, 86.5' RT | | 88.5 |
| 1075+82, 86.5' RT to 1113+06, 91' RT | | 3755 |
| 1113+21, 91' RT to 1142+88, 86' RT | | 2933 |
| TOTAL | | 6777 |