

PAVEMENT MARKING & SIGNING SCHEDULE - SHARED USE PATH

STA	STA	LT/RT	TYPE	LENGTH (FOOT)	72000100 SIGN PANEL - TYPE 1 (SQ FT)	73000100 WOOD SIGN SUPPORT (FOOT)	78001100 PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS (SQ FT)	78001110 PAINT PAVEMENT MARKING - LINE 4" (FOOT)	78001130 PAINT PAVEMENT MARKING - LINE 6" (FOOT)	78001150 PAINT PAVEMENT MARKING - LINE 12" (FOOT)	X0350805 FOLD DOWN BOLLARDS (EACH)
IL 173 *											
1057+00.00	1063+00.00	LT						63.4			
1063+00.00	1069+00.00	LT						138.3			
1069+00.00	1072+00.00	LT						70.0			
1072+00.00	1078+00.00	LT						37.5			
1111+00.00	1117+00.00	RT						11.3			
PERRYVILLE RD. **											
248+00.00	257+30.00	CL		930				172			
	257+22.50	RT							10		
	257+30.00	CL									
	257+24.00	RT	R1-1		2.25	20					
MITCHELL ROAD *											
231+00.00	234+00.00	LT						69.2			
234+00.00	238+75.00	LT						20.7			
MITCHELL STUB											
600+90.90	602+38.50	CL		148				33.9			
	600+42.50	CL									
	600+47.00	LT	R1-1		2.25	20					
	600+48.00	RT	R5-3		4.0	20					
	600+52.50	RT							10		
	600+91.00	CL						30.0			1
BIKE TRAIL PATH											
501+28.15	589+74.50	CL		8846.35				2034.7			
	500+00.00	CL									
	500+07.50	RT							10		
	500+10.00	RT	R5-3		4.0	20					
	500+10.00	LT	R1-1		2.25	20					
	501+10.00	LT	W1-4		2.25						
	501+10.00	LT	R2-1		2.25	20					
	501+28.00	CL						30.0			1
	541+00.00	RT	W2-4		2.25	20					
	541+46.00	LT	W2-4		2.25	20					
	589+73.00	RT	R1-1		2.25	20					
	589+84.00	LT	R5-3		4.0	20					
	589+73.50	CL						25.0			1
	589+76.00	RT							10		
	589+83.74	CL									
ROCK CUT STATE PARK RD											
ROCK CUT STATE PARK RD		CL							52.0		
BICYCLE SYMBOL		CL						40.0			
XING		CL						40.6			
ROCK CUT STATE PARK RD		WEST	W11-1		4.00						
ROCK CUT STATE PARK RD		WEST	W11-15P		3.00	20					
ROCK CUT STATE PARK RD		WEST	W16-2aP		2.00	20					
ROCK CUT STATE PARK RD		WEST	W11-1		4.00	20					
ROCK CUT STATE PARK RD		WEST	W11-15P		3.00	20					
ROCK CUT STATE PARK RD		WEST	W16-7P		2.00	20					
ROCK CUT STATE PARK RD		EAST	W11-1		4.00	20					
ROCK CUT STATE PARK RD		EAST	W11-15P		3.00	20					
ROCK CUT STATE PARK RD		EAST	W16-2aP		2.00	20					
ROCK CUT STATE PARK RD		EAST	W11-1		4.00	20					
ROCK CUT STATE PARK RD		EAST	W11-15P		3.00	20					
ROCK CUT STATE PARK RD		EAST	W16-7P		2.00	20					
TOTALS					66.0	420.0	80.6	2736.0	52.0	40.0	3.0
USE					66	420	81	2736	52	40	3

* 80% FED 20% VMP
** 80% FED 20% COUNTY



USER NAME = \$USER*
DESIGNED - THW
DRAWN - THW
PLOT SCALE = \$SCALE*
PLOT DATE = \$DATE*

REVISOR -
REVISION -
CHECKED - AJK
DATE - 4.30 2013

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
SHARED USE PATH**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	112
CONTRACT NO. 64988			ILLINOIS FED. AID PROJECT	