

| 40600990 TEMPORARY RAMP | | | | |
|-------------------------------------|-------|------------|----------------|---|
| STAGE | WIDTH | LENGTH (*) | AREA | DESCRIPTION |
| | (FT) | (FT) | (SQ YD) | |
| PERRYVILLE ROAD INTERSECTION | | | | |
| 1A | 85 | 16 | 151.1 | ON NORTH LEG OF PERRYVILLE FOR RT TURN MOVEMENT FROM SB PERRYVILLE TO WB IL 173 |
| 1A | 125 | 23 | 319.4 | ON IL 173 WEST OF PERRYVILLE FOR RT TURN MOVEMENT FROM SB PERRYVILLE TO WB IL 173 |
| 1B | 160 | 24 | 426.7 | ON NORTH LEG OF PERRYVILLE FOR NB/SB MOVEMENTS ON PERRYVILLE; USED THRU STAGE 2A |
| 1B | 42 | 40 | 186.7 | ON SOUTH LEG OF PERRYVILLE FOR NB/SB MOVEMENTS ON PERRYVILLE; USED THRU STAGE 2A |
| 1C | 160 | 23 | 408.9 | ON IL 173 EAST OF PERRYVILLE FOR RT TURN MOVEMENT FROM WB IL 173 TO NB PERRYVILLE |
| 2 | 60 | 60 | 400.0 | ON IL 173 EAST OF PERRYVILLE FOR THRU MOVEMENTS ON IL 173; USED THRU STAGE 4 |
| 2A | 120 | 20 | 266.7 | ON IL 173 EAST OF PERRYVILLE FOR RT TURN MOVEMENT FROM NB PERRYVILLE TO EB IL 173 |
| 2B | 90 | 20 | 100.0 | TRIANGULAR SHAPE NEAR CENTER OF INTERSECTION AT PERRYVILLE & IL 173 |
| 2C | 120 | 16 | 213.3 | ON IL 173 WEST OF PERRYVILLE FOR RT TURN MOVEMENT FROM EB IL 173 TO SB PERRYVILLE |
| TOTAL | | | 2,472.8 | |
| USE | | | 2,473 | |

(*) PERPENDICULAR TO THE RISE

| 70103815 TRAFFIC CONTROL SURVEILLANCE | | |
|---|---------------------|--|
| STAGE | DURATION (CAL DAYS) | DESCRIPTION |
| PRESTAGE 1 | 21 | STORM SEWER TRUNK LINE PLACEMENT |
| STAGE 1, 1A, 1B & 1C | 42 | MISC AREAS ALONG IL 173 AT INTERSECTIONS DURING SUBSTAGING; NORTH/SOUTH FOREST HILLS & PERRYVILLE |
| PRESTAGE 2 & 2A STAGE 2, 2A, 2B & 2C | 42 | MISC AREAS ALONG IL 173 AT INTERSECTIONS DURING SUBSTAGING + NORTH/SOUTH FOREST HILLS & PERRYVILLE |
| STAGE 3 & 3A | 12 | MEDIAN & ISLAND CONSTRUCTION AT SIDE ROADS & ENTRANCES |
| STAGE 4 | 6 | MISC AREAS ALONG IL 173 NEAR PERRYVILLE |
| STAGE 5 | 6 | MISC AREAS ALONG IL 173 NEAR PERRYVILLE + MISC OTHER AREAS ALONG IL 173 |
| STAGE 6 & 6A | 6 | MEDIAN & ISLAND CONSTRUCTION AT PERRYVILLE |
| USE | 135 | |

NOTE: MITCHELL ROAD WILL BE CLOSED FOR PART OF PRESTAGE 1 AND STAGE 4.

| 70106800 CHANGEABLE MESSAGE SIGN | | | | |
|----------------------------------|------------------|------------------|--------------------|--|
| STAGE | NO. SIGNS (EACH) | DURATION (WEEKS) | DURATION (CAL MOS) | DESCRIPTION |
| PRESTAGE 1 | 4 | 2 | 2 | SET UP MESSAGE BOARDS ON IL 173 & FOREST HILLS PRIOR TO START-UP OF PRESTAGE 1 |
| STAGE 1 | 6 | 4 | 6 | SET UP MESSAGE BOARDS ON IL 173, FOREST HILLS & PERRYVILLE PRIOR TO SHIFTING TRAFFIC FOR STAGE 1 WORK |
| STAGE 1C & PRESTAGE 2 | 4 | 3 | 3 | SET UP MESSAGE BOARDS ON IL 173 & FOREST HILLS PRIOR TO CLOSING NORTH FOREST HILLS ROAD FOR STAGE 1C AND PRESTAGE 2 WORK |
| STAGE 3 | 4 | 2 | 2 | SET UP MESSAGE BOARDS ON IL 173 & FOREST HILLS PRIOR TO SHIFTING TRAFFIC FOR STAGE 3 WORK |
| STAGE 4 | 4 | 4 | 4 | SET UP MESSAGE BOARDS ON IL 173 & PERRYVILLE PRIOR TO SHIFTING TRAFFIC FOR STAGE 4 WORK |
| STAGE 5 | 4 | 2 | 2 | SET UP MESSAGE BOARDS ON IL 173 & PERRYVILLE PRIOR TO SHIFTING TRAFFIC FOR STAGE 5 WORK |
| STAGE 6 | 4 | 2 | 2 | SET UP MESSAGE BOARDS ON IL 173 & PERRYVILLE PRIOR TO SHIFTING TRAFFIC FOR STAGE 6 WORK |
| TOTAL | | | 21 | |

NOTE: MITCHELL ROAD WILL BE CLOSED FOR PART OF PRESTAGE 1 AND STAGE 4.

FILE NAME = Z00793CVR - 5013.dgn
 MODEL = Defaul.t
 PLOT DRIVER = Vb...IDOT...PDF...1x17.pltcf9



| | | |
|-----------------------------|-----------------------|-----------|
| USER NAME = rgoertz | DESIGNED - RG | REVISED - |
| PLOT SCALE = 20.0000' / in. | DRAWN - TRF | REVISED - |
| PLOT DATE = 5/6/2013 | CHECKED - CMS | REVISED - |
| | DATE - APRIL 30, 2013 | REVISED - |

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

| | | | | |
|---|---------|-----------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 303 | 129R | WINNEBAGO | 968 | 115 |
| CONTRACT NO. 64988 | | | | |
| FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT | | | | |