

40603415						
HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, N50						
STATION	STATION	LOCATION	LENGTH	WIDTH	SOYD	TON
41ST DRIVE CONNECTOR						
531+11.9	534+20.8	RT	332.2	10	369.1	41.3
534+78.7	537+32.6	RT	256.2	10	284.7	31.9
TOTAL						74

40800050						
INCIDENTAL HOT-MIX ASPHALT SURFACING						
STATION	LT / RT	LENGTH	WIDTH 1	WIDTH 2	SO YD	TON
STAGE 2 - COALTOWN ROAD						
16+50.0	LT & RT	10.0	31.1	43.8	41.6	2.9
41ST STREET						
639+97.0	LT & RT	251.8	8.7	9.1	249.0	83.7
642+49.0	LT & RT	56.2	15.1		94.3	31.7
643+05.0	LT & RT	115.4	18.3	18.4	235.5	79.1
644+91.0	LT & RT	52.2	5.9		34.2	11.5
645+44.0	LT & RT	100.3	5.9		65.8	22.1
643+05.0	LT & RT	45.0	25.0	24.5	123.8	13.9
PARKING LOT AT SE CORNER OF 38TH ST AND 41ST AVE DR						
538+40.6	RT	16.2	1.0		1.8	0.3
538+56.5	RT	30.9	1.0		3.4	0.5
538+60.4	RT	25.4	1.0		2.8	0.4
538+81.0	RT	15.4	1.0		1.7	0.2
PARKING LOT ALONG 41ST DRIVE CONNECTOR						
532+15.4	LT	77.8	2.0		17.3	2.4
533+00.7	LT	101.6	2.0		22.6	3.2
38TH STREET (NORTH)						
600+64.4	LT & RT	23.9	7.4	11.4	25.0	9.1
600+88.3	LT & RT	60.9	11.4		77.1	28.1
601+49.2	LT & RT	7.0	11.4	12.0	9.1	3.3
601+56.2	LT & RT	62.8	12.0		83.7	30.5
DRIVEWAYS						
PROPOSED 40TH AVE						
131+35.0	RT	2.9	19.1		6.2	0.9
		10.0	19.1	35.2	30.2	4.2
		4.0	8.8		3.9	0.5
131+76.0	RT	13.3	22.0		32.5	4.6
		10.8	22.0	39.3	36.8	5.1
133+61.0	RT	18.8	12.0		25.1	3.5
		10.0	12.0	32.0	24.4	3.4
132+14.0	LT	6.0	19.0		12.7	1.8
		9.7	19.0	39.0	31.3	4.4
133+07.0	LT	20.2	12.0		26.9	3.8
		10.0	12.0	32.0	24.4	3.4
133+70.0	LT	26.3	12.0		35.1	4.9
		10.0	12.0	32.0	24.4	3.4
135+00	LT	12.0		51.7	34.5	4.8
		12.0	33.3	10.0	28.9	4.0
EXISTING 40TH AVE						
120+70.0	RT	4.5	12.0		54.0	7.6
		10.0	12.0	32.0	24.4	3.4
121+20.0	RT	2.0	12.0		24.0	3.4
		10.0	12.0	32.0	24.4	3.4
121+81.0	RT	4.0	12.0		5.3	0.7
		10.0	12.0	32.0	24.4	3.4
SUBTOTAL						397.6

40800050 (CON'T)						
INCIDENTAL HOT-MIX ASPHALT SURFACING						
STATION	LT / RT	LENGTH	WIDTH 1	WIDTH 2	SO YD	TON
122+34.0	RT	9.3	12.0		12.4	1.7
		10.0	12.0	32.0	24.4	3.4
123+13.0	RT	13.3	16.0		23.6	3.3
		10.0	16.0	36.0	28.9	4.0
123+63.0	RT	10.0	12.0		13.3	1.9
		14.0	12.0	36.0	37.3	5.2
124+26.0	RT	14.3	68.6	41.4	87.4	12.2
		14.3	28.7		22.8	3.2
		14.3	12.7		10.1	1.4
COALTOWN ROAD						
10+25.0	LT	14.5	12.3		9.9	1.4
10+80.0	RT	82.6	22.0		101.0	14.1
14+44.0	LT	86.7	12.0		57.8	8.1
		13.9	12.0	16.6	22.1	3.1
SUBTOTAL						63.2
TOTAL						461

FILE NAME: c:\p\proj\080319\08\contract\1\Design\Misc_Sheets\0264884-ahf-Sched10.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
6507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.776.4009 Fax 773.776.4014

USER NAME = ntumbv	DESIGNED -	REVISED - ADDENDUM 1 8/15/2013
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = 8/14/2013	DATE - 8/14/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	44
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				