

42000401						
PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)						
STATION	STATION	LOCATION	LENGTH	WIDTH 1	WIDTH 2	SO YD
38TH STREET - SOUTH						
149+90	150+68	FULL WIDTH	78.0	23.1	35.4	253.5
150+68	150+75	FULL WIDTH	7.0	35.4	36.5	28.0
150+75	150+93	FULL WIDTH	18.0	36.5	50.6	87.1
150+93	150+98	FULL WIDTH	5.0	50.6	61.3	31.1
150+98	151+01	FULL WIDTH	3.0	61.3	76.1	22.9
151+01	151+12	FULL WIDTH	11.0	103.9	134.5	145.7
151+12	151+33	FULL WIDTH	21.0	154.1	154.2	359.7
151+33	151+36	FULL WIDTH	3.0	154.2	137.7	48.7
151+36	151+47	FULL WIDTH	11.0	137.7	85.9	136.6
151+47	151+51	FULL WIDTH	4.0	85.9	77.6	36.3
151+51	151+84	FULL WIDTH	33.0	77.6	49.9	233.8
151+84	151+88	FULL WIDTH	4.0	49.9	49.8	22.2
151+88	152+32	FULL WIDTH	44.0	49.8		243.5
152+32	153+08	FULL WIDTH	76.0	49.8	56.0	446.7
153+08	153+58	FULL WIDTH	50.0	56.0		311.1
153+58	153+68	FULL WIDTH	10.0	56.0	55.2	61.8
153+68	153+78	FULL WIDTH	10.0	55.2	55.1	61.3
153+78	153+96	FULL WIDTH	18.0	55.1	57.6	112.7
153+96	154+05	FULL WIDTH	9.0	57.6	59.9	58.8
154+05	154+16	FULL WIDTH	11.0	59.9	64.0	75.7
154+16	154+37	FULL WIDTH	21.0	64.0	84.8	173.6
154+37	154+43	FULL WIDTH	6.0	84.8	96.9	60.6
154+43	154+51	FULL WIDTH	8.0	96.6	117.9	95.3
154+51	154+60	FULL WIDTH	9.0	117.9	201.3	159.6
155+14	155+25	FULL WIDTH	11.0	242.3	132.4	229.0
155+25	155+40	FULL WIDTH	15.0	132.4	88.8	184.3
155+40	155+60	FULL WIDTH	20.0	88.8	67.3	173.4
155+60	155+77	FULL WIDTH	17.0	67.3	59.8	120.0
155+77	156+00	FULL WIDTH	23.0	59.8	54.2	145.7
156+00	156+25	FULL WIDTH	25.0	54.2	50.2	145.0
156+25	156+63	FULL WIDTH	38.0	50.2	48.0	207.3
156+63	156+80	FULL WIDTH	17.0	48.0		90.7
PROPOSED 40TH AVENUE						
134+50	135+38	FULL WIDTH	88.0	25.2	32.0	279.6
135+38	135+55	FULL WIDTH	17.0	32.0	33.5	61.9
135+55	135+84	FULL WIDTH	29.0	33.5	34.1	108.9
135+84	136+08	FULL WIDTH	24.0	34.1	35.7	93.1
136+08	136+50	FULL WIDTH	42.0	35.7	43.3	184.3
136+50	136+73	FULL WIDTH	23.0	43.3	50.3	119.6
136+73	136+81	FULL WIDTH	8.0	50.3	53.7	46.2
136+81	136+95	FULL WIDTH	14.0	53.7	65.0	92.3
136+95	137+05	FULL WIDTH	10.0	65.0	79.2	80.1
137+05	137+15	FULL WIDTH	10.0	79.2	102.0	100.7
137+15	137+19	FULL WIDTH	4.0	102.0	138.5	53.4
41ST AVENUE DRIVE						
185+56	194+39	FULL WIDTH	883.0	36.0		3,532.0
194+39	194+66	FULL WIDTH	27.0	36.0	37.9	110.9
194+66	195+91	FULL WIDTH	125.0	37.9	50.6	614.6
195+91	196+43	FULL WIDTH	52.0	50.6	60.7	321.5
196+43	196+66	FULL WIDTH	23.0	60.7	67.8	164.2
196+66	196+77	FULL WIDTH	11.0	67.8	71.4	85.1
196+77	197+40	FULL WIDTH	63.0	71.4	82.5	538.7
197+40	198+36	FULL WIDTH	96.0	82.5	69.3	809.6
198+36	198+78	FULL WIDTH	42.0	69.3	58.0	297.0
198+78	198+94	FULL WIDTH	16.0	58.0	59.2	104.2
198+94	199+04	FULL WIDTH	10.0	59.2	61.1	66.9
199+04	199+19	FULL WIDTH	15.0	61.1	66.1	106.0
199+19	199+28	FULL WIDTH	9.0	66.1	72.1	69.1
199+28	199+40	FULL WIDTH	12.0	72.1	86.8	105.9
SUBTOTAL						12,707.3

42000401 (CON'T)						
PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)						
STATION	STATION	LOCATION	LENGTH	WIDTH 1	WIDTH 2	SO YD
41ST DRIVE CONNECTOR						
520+23	520+34	FULL WIDTH	11.0	146.0	96.3	148.1
520+34	520+44	FULL WIDTH	10.0	96.3	75.6	95.5
520+44	520+54	FULL WIDTH	10.0	75.6	62.8	76.9
520+54	520+64	FULL WIDTH	10.0	62.8	54.1	64.9
520+64	520+74	FULL WIDTH	10.0	54.1	47.9	56.7
520+74	520+84	FULL WIDTH	10.0	47.9	44.1	51.1
520+84	520+91	FULL WIDTH	7.0	44.1	41.5	33.3
520+91	521+33	FULL WIDTH	42.0	41.5	38.0	185.5
521+33	522+16	FULL WIDTH	83.0	38.0		350.4
522+16	522+55	FULL WIDTH	39.0	38.0	36.5	161.4
522+55	522+94	FULL WIDTH	39.0	36.5	32.0	148.4
522+94	523+15	FULL WIDTH	21.0	32.0	29.1	71.3
527+61	528+03	FULL WIDTH	42.0	38.1	40.0	182.2
528+03	529+90	FULL WIDTH	187.0	40.0	49.4	928.8
529+90	530+17	FULL WIDTH	27.0	49.4	58.1	161.3
530+17	531+12	FULL WIDTH	95.0	58.1	55.3	598.5
531+12	531+45	FULL WIDTH	33.0	55.3	42.9	180.0
531+45	531+85	FULL WIDTH	40.0	42.9	38.0	179.8
531+85	534+16	FULL WIDTH	231.0	38.0		975.3
534+16	535+16	FULL WIDTH	100.0	38.0	45.1	461.7
535+16	535+85	FULL WIDTH	69.0	45.1	50.0	364.6
535+85	536+44	FULL WIDTH	59.0	50.0		327.8
536+44	537+09	FULL WIDTH	65.0	50.0		361.1
537+09	538+85	FULL WIDTH	176.0	43.7	43.9	856.5
538+85	539+13	FULL WIDTH	28.0	54.9		170.8
539+13	539+63	FULL WIDTH	50.0	54.9	55.0	305.3
539+63	540+00	FULL WIDTH	37.0	55.0	53.5	223.0
540+00	540+34	FULL WIDTH	34.0	53.5	50.6	196.6
540+34	540+66	FULL WIDTH	31.5	50.6	52.0	179.7
39TH STREET						
140+19	140+27	FULL WIDTH	8.0	119.4	66.5	82.6
140+27	140+38	FULL WIDTH	11.0	66.5	50.1	71.3
140+38	140+48	FULL WIDTH	10.0	50.1	41.3	50.8
140+48	140+68	FULL WIDTH	20.0	41.3	32.2	81.7
140+68	140+90	FULL WIDTH	22.0	32.2	26.9	72.2
140+90	141+10	FULL WIDTH	20.0	26.9	24.3	56.9
141+10	141+60	FULL WIDTH	50.0	24.3	23.7	133.3
COAL TOWN ROAD						
10+00	10+48	RT	48.0	1.0		5.3
10+48	11+36	RT	88.0	1.0	8.3	45.5
11+36	12+23	RT	87.0	8.3	16.2	118.4
12+23	13+68	RT	145.0	16.2	19.8	290.0
13+68	15+14	RT	146.0	19.8	21.9	338.2
15+14	15+50	RT	36.0	21.9	12.1	68.0
15+50	15+75	RT	25.0	12.1	8.3	28.3
15+75	16+04	RT	29.0	8.3	7.0	24.7
16+04	16+50	RT	46.0	7.0		35.8
16+50	18+19	FULL WIDTH	169.0	38.0		713.6
18+19	19+04	FULL WIDTH	85.0	38.0	44.0	387.2
19+04	19+92	FULL WIDTH	88.0	44.0	50.0	459.6
19+92	22+88	FULL WIDTH	296.0	50.0		1,644.4
22+88	23+29	FULL WIDTH	41.0	50.0	41.1	207.5
23+29	23+72	FULL WIDTH	43.0	41.1	38.0	189.0
23+72	30+00	FULL WIDTH	628.0	38.0		2,651.6
35TH STREET						
5+19	5+29	FULL WIDTH	10.0	100.5	64.8	91.8
5+29	5+39	FULL WIDTH	10.0	64.8	44.2	60.6
5+39	5+49	FULL WIDTH	10.0	44.2	36.3	44.7
5+49	5+59	FULL WIDTH	10.0	36.3	34.5	39.3
5+59	5+65	FULL WIDTH	6.0	34.5		23.0
SUBTOTAL						16,111.7

FILE NAME: n:\p\proj\0802393\08\cont\act\1\Design\Misc_Sheets\026484-akt_Schwell.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
6507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = ntumbv	DESIGNED -	REVISED - ADDENDUM 1 8/15/2013
PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 8/14/2013	CHECKED -	REVISED -
	DATE - 8/14/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.
--------	-----------	-----------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	45
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				