

STORM SEWER SCHEDULE				550A0050	550A0070	550A0120	550A0340	550A0360	550A0380	550A0410	550A0420	Z0056608	Z0056610	Z0056612	Z0056614	Z0056616	60107600	20800150	
PIPE NO	FROM STR STA	TO STR STA	PIPE SLOPE	STORM SEWERS, CLASS A, TYPE 1 12"	STORM SEWERS, CLASS A, TYPE 1 15"	STORM SEWERS, CLASS A, TYPE 1 24"	STORM SEWERS, CLASS A, TYPE 2 12"	STORM SEWERS, CLASS A, TYPE 2 15"	STORM SEWERS, CLASS A, TYPE 2 18"	STORM SEWERS, CLASS A, TYPE 2 24"	STORM SEWERS, CLASS A, TYPE 2 27"	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 21 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	PIPE UNDERDRAINS 4"	TRENCH BACKFILL	
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
117	14+10 RT	13+35 RT	0.48%				75											3.7	
118	15+10 LT	13+35 LT															171		
119	13+35 RT	14+00 RT															72		
120	14+70 LT	15+10 LT	0.61%									33						4.2	
121	16+10 LT	15+10 LT	0.92%									93						9.3	
122	15+10 LT	15+16 RT	0.54%					57										8.0	
123	15+16 RT	15+19 RT	22.47%					17											
124	15+19 RT	15+25 RT	1.09%					23											
125	16+10 RT	15+16 RT	1.34%				87												
126	15+10 LT	17+90 LT															269		
127	15+16 RT	17+90 RT															265		
128	18+16 RT	18+33 LT															59		
129	18+32 LT	18+93 LT	1.67%									58						7.2	
130	18+93 LT	19+85 LT	3.05%									85							
131	17+90 RT	20+75 RT															289		
132	18+95 RT	19+85 RT	3.90%				84											10.0	
133	19+85 LT	19+85 RT	0.94%				54											6.1	
134	19+85 RT	20+75 RT	3.49%					83										10.1	
135	18+93 LT	21+65 LT															277		
136	20+75 RT	21+65 RT	2.61%										82						
137	21+65 LT	21+65 RT	0.62%					63										7.3	
138	20+75 RT	21+65 RT															88		
139	21+65 RT	22+70 RT	0.91%							102								1.1	
140	21+65 LT	22+62 LT															93		
141	21+65 RT	22+70 RT															103		
142	21+66 LT	21+66 RT															60		
143	22+62 LT	22+70 RT	1.78%							63								0.6	
144	22+62 LT	22+70 RT															66		
145																			
146	22+62 LT	24+95 LT															227		
147	22+70 RT	24+95 RT															224		
148	22+70 RT	22+86 RT	0.84%								32								
148A	23+75 LT	22+62 LT	0.58%												109			0.7	
149	24+95 RT	24+95 LT	0.49%				43											4.8	
149A	24+95 LT	23+75 LT	0.59%											116				8.7	
150	24+95 LT	26+95 LT															199		
151	24+95 RT	26+95 RT															200		
152	26+95 LT	24+95 LT	0.76%									194						23.8	
153	26+95 RT	26+95 LT	0.49%				43											4.5	
153A	21+65 LT	21+65 LT	0.56%									9							
153B	22+62 LT	22+62 LT	0.56%									9							
153C	23+75 LT	23+75 LT	0.56%									9							
153D	24+95 LT	24+95 LT	0.56%									9							
38TH STREET NORTH																			
154	163+00 LT	163+00 RT	0.54%				46											5.2	
155	163+00 RT	162+25 RT	6.32%									68						6.0	
156	162+25 RT	162+04 RT	3.46%									41							
SUBTOTAL				0	0	0	432	180	0	165	32	608	145	116	109	0	2662	121.2	
TOTAL				355	57	555	2261	671	351	684	32	1286	484	116	109	201	7923	970.9	
																		TOTAL TRENCH BACKFILL FROM PIPE CULVERT SCHEDULE	459.9
																		TOTAL TRENCH BACKFILL (ROUNDED CU YDS)	1431

FILE NAME: N:\PROJ\000393\00\CONTRACT\1\Design\Misc_Sheets\026484-ent-Sched25.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = odow	DESIGNED -	REVISED - ADDENDUM 1 8/15/2013
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / 1"	CHECKED -	REVISED -
PLOT DATE = 8/14/2013	DATE - 8/14/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.
--------	-----------	----	--------	------	----	------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	59
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				