

78009012					
MODIFIED URETHANE PAVEMENT MARKING - LINE 12"					
STATION	OFFSET	STATION	OFFSET	TYPE	FOOT
38th STREET					
149+88	0.0 LT	150+76	0.0 LT	12" SOLID YELLOW	54.0
156+65	1.9 RT	157+42	26.0 LT	12" SOLID YELLOW	46.0
158+02	28.0 LT	159+62	73.0 LT	12" SOLID WHITE	570.0
160+43	45.0 RT	161+84	0.0 LT	12" SOLID WHITE	650.0
41st DRIVE CONNECTOR					
528+00	0.0 LT	530+22	0.0 LT	12" SOLID YELLOW	82.0
41st AVENUE DRIVE					
195+91	24.0 LT	199+66	92.0 LT	12" SOLID WHITE	202.0
196+25	0.0 LT	198+63	1.0 RT	12" SOLID YELLOW	86.0
540+20	4.0 RT	543+95	0.0 LT	12" SOLID YELLOW	145.0
COALTOWN ROAD					
11+30	0.0 LT	13+89	3.7 RT	12" SOLID YELLOW	114.0
16+72	4.0 RT	18+34	0.0 LT	12" SOLID YELLOW	55.0
18+93	0.0 LT	21+37	0.0 LT	12" SOLID YELLOW	162.0
24+15	4.0 RT	28+19	0.0 LT	12" SOLID YELLOW	157.0
25+79	19.0 RT	27+00	19.0 RT	12" SOLID WHITE	10.0
25+82	19.0 LT	31+60	12.0 LT	12" SOLID WHITE	193.0
27+84	19.0 RT	31+60	12.0 RT	12" SOLID WHITE	155.0
TOTAL					2,681

78100100			
RAISED REFLECTIVE PAVEMENT MARKER			
STATION	STATION	TYPE	EACH
40th AVENUE			
134+49	136+93	2-WAY AMBER	18
135+78	136+93	1-WAY	6
41st AVENUE DRIVE			
185+56	186+67	1-WAY	6
185+56	199+35	2-WAY AMBER	79
196+31	199+35	1-WAY	15
538+51	540+00	1-WAY	8
538+51	540+00	1-WAY	8
538+51	544+14	2-WAY AMBER	35
COALTOWN ROAD			
10+00	13+89	2-WAY AMBER	23
12+23	13+76	1-WAY	7
15+07	16+52	1-WAY	7
15+07	18+34	2-WAY AMBER	24
18+93	21+37	2-WAY AMBER	19
19+92	21+37	1-WAY	7
22+59	24+04	1-WAY	8
22+59	30+00	2-WAY AMBER	46
TOTAL			316

78300100						
PAVEMENT MARKING REMOVAL						
STATION	STATION	LOCATION	LENGTH	WIDTH (INCH)	TYPE	SO FT
STAGE 1						
COALTOWN ROAD						
8+80	11+00	CL	220	4	DBL	146.7
11+00	17+06	LT	606	4	DBL	404.0
11+00	17+06	RT	606	4	DBL	404.0
17+06	18+30	LT	124	4	DBL	82.7
17+06	18+30	LT	124	4	SOLID	41.3
17+10		CL			LT SYMBOL	15.2
17+60		CL			ONLY SYMBOL	21.1
18+13		CL			LT SYMBOL	15.2
STAGE 4						
41ST DRIVE CONNECTOR						
538+45		LT	10	24	SOLID	20.0
538+76	540+18	LT	142	4	SKIP DASH	23.7
STAGE 5						
41ST DRIVE CONNECTOR						
540+66	543+42	RT	276	4	SKIP DASH	46.0
540+66	543+42	RT	276	4	DBL	184.0
38TH STREET (SOUTH)						
158+15		RT			LT SYMBOL	15.2
158+80		RT			ONLY SYMBOL	21.1
159+05		RT			LT SYMBOL	15.2
158+20		RT			LT/THRU/RT SYBMO	33.9
20% CONTINGENCY						
						297.8
TOTAL						1,788

78009024					
MODIFIED URETHANE PAVEMENT MARKING - LINE 24"					
STATION	OFFSET	STATION	OFFSET	TYPE	FOOT
40th AVENUE					
150+99	30.0 LT	151+21	30.0 LT	24" SOLID WHITE	22.0
151+18	38.0 RT	151+47	38.0 RT	24" SOLID WHITE	29.0
154+27	6.0 LT	154+28	39.0 RT	24" SOLID WHITE	40.0
155+49	6.0 RT	155+49	37.0 LT	24" SOLID WHITE	45.0
163+29	0.0 RT	163+34	33.0 RT	24" SOLID WHITE	36.0
40th AVENUE					
136+93	0.0 RT	136+93	28.0 RT	24" SOLID WHITE	28.0
821+29	0.0 LT	821+29	34.0 LT	24" SOLID WHITE	28.0
41st DRIVE CONNECTOR					
520+42	13.0 LT	520+53	41.0 LT	24" SOLID WHITE	30.0
520+51	13.5 LT	520+51	1.0 LT	24" SOLID WHITE	12.0
530+22	6.5 RT	530+18	40.0 RT	24" SOLID WHITE	35.0
531+11	6.0 RT	531+11	19.0 LT	24" SOLID WHITE	25.0
534+32	36.0 LT	534+47	35.0 LT	24" SOLID WHITE	18.0
537+39	6.0 LT	537+39	42.0 RT	24" SOLID WHITE	48.0
41st AVENUE DRIVE					
199+35	1.0 RT	199+35	42.0 RT	24" SOLID WHITE	41.0
538+51	6.0 RT	538+56	39.0 LT	24" SOLID WHITE	47.0
COALTOWN ROAD					
13+76	7.0 RT	13+76	32.5 RT	24" SOLID WHITE	25.0
15+07	6.0 RT	15+07	19.0 LT	24" SOLID WHITE	25.0
21+37	6.0 RT	21+37	31.0 RT	24" SOLID WHITE	25.0
22+59	6.0 RT	22+59	19.0 LT	24" SOLID WHITE	25.0
EXISTING 41ST STREET					
641+00	8.8 RT	641+00	34.0 RT	24" SOLID WHITE	25.0
643+15	9.3 LT	643+15	34.0 LT	24" SOLID WHITE	25.0
35th STREET					
5+44	10.0 RT	5+44	16.6 LT	24" SOLID WHITE	26.0
TOTAL					660

78200410				
GUARDRAIL MARKERS, TYPE A				
STATION	STATION	LOCATION	LENGTH	EACH
JOHN DEERE ROAD				
266+16	268+04	RT	188.0	4
TOTAL				4

78200520				
BARRIER WALL MARKERS, TYPE B				
STATION	STATION	LOCATION	LENGTH	EACH
41ST DRIVE CONNECTOR				
521+33	526+61	LT	528.0	14
526+61	532+25	LT	564.0	22
520+39	527+33	RT	694.0	18
527+33	530+23	RT	290.0	12
TOTAL				66

78201000		
TERMINAL MARKER - DIRECT APPLIED		
STATION	LOCATION	EACH
41ST DRIVE CONNECTOR		
265+66	RT	1
TOTAL		1

78300200		
RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		
STATION	STATION	EACH
COALTOWN ROAD		
8+00	16+50	22
TOTAL		22

84200804			
REMOVAL OF POLE FOUNDATION			
STATION	OFFSET	LOCATION	EACH
41ST AVENUE DRIVE			
192+14	24.0	RT	1
192+43	9.6	RT	1
193+04	17.7	RT	1
193+48	18.0	RT	1
194+38	30.0	LT	1
194+66	30.2	LT	1
TOTAL			6

89502385			
REMOVE EXISTING CONCRETE FOUNDATION			
STATION	OFFSET	LOCATION	EACH
41ST AVENUE DRIVE			
192+16	10.4	RT	1
192+23	10.1	RT	1
192+31	10.5	RT	1
192+39	12.5	RT	1
40TH AVE (EXISTING ALIGNMENT)			
125+70	36.2	LT	1
TOTAL			5

X0322918		
PROPOSED MANHOLE/CATCH BASIN CONNECTION OVER EXISTING SS		
LOCATION	EACH	
41ST DRIVE CONNECTOR		
532+83	33.19 L	1
TOTAL		1

FILE NAME: c:\p\proj\08003193\08\contract\1\design\misc\sheets\026884-ant-sched05.dgn



USER NAME = espino	DESIGNED -	REVISED -
PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 3/11/2013	CHECKED -	REVISED -
	DATE - 3/11/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.
--------	-----------	----	--------	------	----	------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	69
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				