

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE										
				80% FED 20% STATE							80% FED 20% CITY		100% CITY	
				ROADWAY	ROADWAY	BRIDGE	SAFETY	RETAINING WALL	RETAINING WALL	OTHER	RETAINING WALL	SAFETY		
				0001	0004	0008	0021	0040	0040	0044	0040	0021		
URBAN	URBAN	081-0176	URBAN	081-7002	081-7003	URBAN	081-P002	081-P003	URBAN					
50200100	STRUCTURE EXCAVATION	CU YD	205			91						114		
50300225	CONCRETE STRUCTURES	CU YD	701			221.1				155.1		324.8		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1395.1			428.1		424.5		542.5				
50300260	BRIDGE DECK GROOVING	SQ YD	809			809								
50300285	FORM LINER TEXTURED SURFACE	SQ FT	6586							791		5795		
50300300	PROTECTIVE COAT	SQ YD	3519			1446		499		930		644		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1								
50500505	STUD SHEAR CONNECTORS	EACH	4924			2916						2008		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	314800			146020		53970		81200		33610		
50800515	BAR SPLICERS	EACH	96			96								
50901720	BICYCLE RAILING	FOOT	744			60		285		399				
50901735	BRIDGE FENCE RAILING (SIDEWALK)	FOOT	183			183								
50901750	PARAPET RAILING	FOOT	946			243		352		351				
51201610	FURNISHING STEEL PILES HP12X63	FOOT	320			320								
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	499							66		433		
51202305	DRIVING PILES	FOOT	320			320								
51500100	NAME PLATES	EACH	4			1		1		1		1		

* DENOTES SPECIALITY ITEM

FILE NAME: \\s\proj\080313\08\contract\1\design\misc\sheet\028-084-rt-50086.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60655
Tel: 773.776.4000 Fax: 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
PLOT SCALE = 100.0000' / 1"	DRAWN -	REVISED -
PLOT DATE = 9/18/2013	CHECKED -	REVISED -
	DATE = 9/18/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 595	SECTION (142-1R & 142-1HB)	COUNTY ROCK ISLAND	TOTAL SHEETS 507	SHEET NO. 8
CONTRACT NO. 64884				
ILLINOIS FED. AID PROJECT				