


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				URBAN	80% FED 20% STAT ROADWAY	80% FED 20% STATE BRIDGE	80% FED 20% STATE BRIDGE	80% FED 20% STATE BRIDGE	80% FED 20% STATE BRIDGE	100% CITY	
					0004 S.N.	0011 101-0195	0011 101-0196	0011 101-0197	0011 101-0198	0011 CITY OF ROCKFORD	
28000305	TEMPORARY DITCH CHECKS	FOOT	1,005		1,005						
28000400	PERIMETER EROSION BARRIER	FOOT	3,247		3,247						
28000500	INLET AND PIPE PROTECTION	EACH	9		9						
28001000	AGGREGATE (EROSION CONTROL)	TON	114		114						
28100105	STONE RIPRAP, CLASS A3	SO YD	70		70						
28100109	STONE RIPRAP, CLASS A5	SO YD	3305	△		820	820	832.5	832.5		△
28200200	FILTER FABRIC	SO YD	3375		70	820	820	832.5	832.5		
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	11,348		11,348						
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SO YD	2,470		2,470						
31200100	STABILIZED SUBBASE 4"	SO YD	1,158		1,158						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	12		12						
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	2,433		2,433						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1,833		1,833						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,006		1,006						

△ DENOTES SPECIALTY ITEM  
 \*\* 100% STATE

△ Rev. 10-29-13

FILE NAME : D:\2013\11-15-13\11-15-13.dwg  
 PLOT DATE : 11/15/2013 10:11:17 AM

 QUIGG ENGINEERING INC	USER NAME : rgoertz PLOT SCALE : 40.0000 / 1" = 40' PLOT DATE : 9/3/2013	DESIGNED - CMS DRAWN - TKW CHECKED - CMS DATE - 07/01/2013	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b> SCALE: SHEET NO. OF SHEETS STA. TO STA.	F.A.P. RTE. 301 SECTION 3BR & 3BR-1 COUNTY WINNEBAGO TOTAL SHEETS 290 SHEET NO. 7 CONTRACT NO. 64019 FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT
--	--	---	--	---	---	--