

78300100 PAVEMENT MARKING REMOVAL									
SO FT	STA	OFFSET	STA	OFFSET	LOCATION	PLACEMENT	FOOT	IN	REMARKS
US 20									
444	882+00.00	32.0	917+50.00	32.0	EB CENTER	25%	887.5	6	SKIP-DASH
286	908+93.50	20.0	917+50.00	20.0	EB LEFT EDGE	100%	856.5	4	SOLID
138	939+00.00	32.0	950+00.00	32.0	EB CENTER	25%	275.0	6	SKIP-DASH
205	941+00.00	20.0	947+14.00	20.0	EB LEFT EDGE	100%	614.0	4	SOLID
272	941+00.00	44.0	949+15.00	44.0	EB RIGHT EDGE	100%	815.0	4	SOLID
71	905+75.00	-44.0	906+75.00	-11.0	WB GORE	100%	105.4	8	SOLID
72	905+75.00	-51.6	906+75.00	-11.0	WB GORE	100%	108.0	8	SOLID
1,640	906+90.00	-20.0	956+08.00	-20.0	WB LEFT EDGE	100%	4,918.0	4	SOLID
783	906+90.00	-32.0	969+50.00	-32.0	WB CENTER	25%	1,565.0	6	SKIP-DASH
1,957	910+80.00	-44.0	969+50.00	-44.0	WB RIGHT EDGE	100%	5,870.0	4	SOLID
IL 2									
218	238+58.80	27.0	245+10.00	14.0	NB LEFT EDGE	100%	651.4	4	SOLID
172	246+44.00	34.3	249+01.00	25.4	NB GORE	100%	257.2	8	SOLID
25	243+58.50	-2.2	244+32.00	-2.2	SB LEFT EDGE	100%	73.5	4	SOLID
51	242+00.00	-16.6	246+00.00	-13.7	SB CENTER	25%	100.1	6	SKIP-DASH
52	243+45.00	-25.4	245+00.00	-25.5	SB RIGHT EDGE	100%	155.1	4	SOLID
6,386	TOTAL								

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL					
EACH	LOCATION	OFFSET	SPACING	NO	REMARKS
US 20					
170	882+00.00	950+00.00	EB CENTER	80	2
160	906+00.00	970+00.00	WB CENTER	80	2
IL 2					
25	232+50.00	252+50.00	NB CENTER	80	1
4	239+88.00	240+75.00	NB GORE	40	2
10	246+50.00	248+50.00	NB GORE	40	2.0
11	242+00.00	250+50.00	SB CENTER	80	1
380	TOTAL				

89000200 TEMPORARY TRAFFIC SIGNAL INSTALLATION	
L SUM	LOCATION
1.0	STAGE 1 & 2 ON IL 2 AT TEMP RAMP CONNECTORS E & F
1.0	TOTAL
NOTE:SEE SPECIAL PROVISIONS	

Z0028415 GEOTECHNICAL REINFORCEMENT						
SO YD	LOCATION	OFFSET	LENGTH	WIDTH	SO FT	REMARKS
US 20						
1,193	925+60.61	927+71.22	EB	210.61	51	10741.11
992	925+96.08	927+71.22	WB	175.14	51	8932.14
2,185	TOTAL					

Z0062456 TEMPORARY PAVEMENT						
SO YD	LOCATION	WIDTH	STAGE	SO FT	REMARKS	
US 20						
1,493	924+50.00	929+00.00	29.85	PRE 1B	13,432.50	MEDIAN BETWEEN STRUCTURES
525	924+50.00	929+00.00	10.50	1	4,725.00	MEDIAN BETWEEN STRUCTURES
2,018	TOTAL					

Z0065752 SLOTTED DRAIN 12" WITH 6" SLOT			
FOOT	LOCATION	REMARKS	
US 20			
57	944+12.00	944+68.50	EAST CROSSOVER
57	TOTAL		

Z0065765 SLOTTED DRAIN 18" WITH VARIABLE SLOT			
FOOT	LOCATION	REMARKS	
US 20			
154	911+39.80	912+93.80	WEST CROSSOVER
154	TOTAL		

A2000114 TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	
EACH	
31	ESTIMATED QUANTITY

A2001714 TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	
EACH	
31	ESTIMATED QUANTITY

A2002914 TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 1-3/4" CALIPER, BALLED AND BURLAPPED	
EACH	
31	ESTIMATED QUANTITY

A2006514 TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	
EACH	
31	ESTIMATED QUANTITY

A2006714 TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	
EACH	
31	ESTIMATED QUANTITY

B2004114 TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	
EACH	
32	ESTIMATED QUANTITY

B2005014 TREE, MALUS SNOWDRIFT (SNOWDRIFT CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	
EACH	
31	ESTIMATED QUANTITY

K1005421 SEEDING (SPECIAL)					
ACRE	LOCATION	LT/RT	SO FT	REMARKS	
US 20					
0.09	921+50.00	922+50.00	LT	4,047	AREA OF WETLAND TEMPORARILY IMPACTED
0.08	921+00.00	922+00.00	RT	3,540	AREA OF WETLAND TEMPORARILY IMPACTED
0.17	TOTAL				
0.25	USE				
• AREA MEASURED IN CADD					

X0322288 MEDIAN CLOSURE			
EACH	LOCATION	REMARKS	
US 20			
1	912+16.78	PR CROSSOVER	
1	943+63.28	EX CROSSOVER	
2	TOTAL		

X0322392 BEVELED PIPE AND GUARD			
EACH	LOCATION	DIA	REMARKS
US 20			
1	910+27.00	18"	
1	914+04.50	18"	
1	945+79.30	12"	
3	TOTAL		

X0322936 REMOVE EXISTING FLARED END SECTION			
EACH	LOCATION	REMARKS	
US 20			
1	945+39.50		
1	TOTAL		

X2011000 TEMPORARY FENCE (SPECIAL)					
FOOT	LOCATION	LT/RT	REMARKS		
US 20					
175	921+25.00	923+00.	LT	ALONG CONSTRUCTION LIMITS ADJACENT TO WETLAND TO DELINEATE	
150	920+25.00	921+75.	RT	ALONG CONSTRUCTION LIMITS ADJACENT TO WETLAND TO DELINEATE	
325	TOTAL				

X4400110 TEMPORARY PAVEMENT REMOVAL						
SO YD	LOCATION	WIDTH	STAGE	SO FT	REMARKS	
US 20						
1,493	924+50.00	929+00.00	29.85	PRE 1B	13,432.50	MEDIAN BETWEEN STRUCTURES
525	924+50.00	929+00.00	10.50	1	4,725.00	MEDIAN BETWEEN STRUCTURES
2,018	TOTAL					

X6380205 TEMPORARY MODULAR GLARE SCREEN				
FOOT	LOCATION	STAGE	REMARKS	
US 20				
450	911+50.00	916+00.00	1	
450	938+00.00	942+50.00	2	
900	TOTAL			

X7050167 TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)					
EACH	LOCATION	OFFSET	STAGE	REMARKS	
US 20					
1	916+69.26	917+19.26	16' LT	PRE 1A	WB DEPART - LT SIDE
1	936+20.12	936+70.12	16' RT	1	EB - LT SIDE
2	TOTAL				

X7050169 TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED					
EACH	LOCATION	OFFSET	STAGE	REMARKS	
US 20					
1	927+41.10	927+91.10	16' LT	PRE1B	EB APPR - RT SIDE
1	TOTAL				

X8410102 TEMPORARY LIGHTING SYSTEM	
L SUM	LOCATION
US 20	
0.5	ALONG WEST CROSS-OVER
0.5	ALONG EAST CROSS-OVER
1.0	TOTAL

#2000291 REAL-TIME TRAFFIC CONTROL CENTRAL BASE UNIT				
MONTHS	DIRECTION	NUMBER OF CALENDAR LOCATIONS	MONTHS	REMARKS
9	BOTH	1	9	YEAR 1
8	BOTH	1	8	YEAR 2
17	TOTAL			

#2000292 REAL-TIME TRAFFIC CONTROL SENSOR UNIT				
MONTHS	DIRECTION	NUMBER OF CALENDAR LOCATIONS	MONTHS	REMARKS
27	EB	3	9	YEAR 1
27	WB	3	9	YEAR 1
24	WB	3	8	YEAR 2
78	TOTAL			

IL 2 TO US 20 EASTBOUND SHALL HAVE SIGNS AND FLASHERS INCLUDED IN THE SENSOR UNIT  
 IL 251 NORTHBOUND TO US 20 WESTBOUND SHALL HAVE SIGNS AND FLASHERS INCLUDED IN THE SENSOR UNIT  
 IL 251 SOUTHBOUND TO US 20 EASTBOUND SHALL HAVE SIGNS AND FLASHERS INCLUDED IN THE SENSOR UNIT

FILE NAME = D264019-ah-t-Schedule.dgn  
 MODEL = Default  
 PLOT DRIVER = VBA\_IIDOT\_PDF...11x17.pltcf9



USER NAME = rgoertz	DESIGNED - RG	REVISED -
	DRAWN - KEC	REVISED -
PLOT SCALE = 48.0000' / in.	CHECKED - CMS	REVISED -
PLOT DATE = 8/16/2013	DATE - 07/01/2013	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES				
SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	3BR & 3BR-1	WINNEBAGO	290	27
CONTRACT NO. 64D19				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				