

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				80% FED 20% STAT ROADWAY 0004 S.N.	80% FED 20% STATE BRIDGE 0011 101-0195	80% FED 20% STATE BRIDGE 0011 101-0196	80% FED 20% STATE BRIDGE 0011 101-0197	80% FED 20% STATE BRIDGE 0011 101-0198	100% CITY BRIDGE 0011 CITY OF ROCKFORD
				URBAN					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2979.5		726.25	726.25	763.50	763.50	
50300260	BRIDGE DECK GROOVING	SQ YD	8,512.20		2,069.10	2,069.10	2,187.00	2,187.00	
50300265	SEAL COAT CONCRETE	CU YD	701		197.6	197.6	152.90	152.90	
50300280	CONCRETE ENCASEMENT	CU YD	33.80		16.90	16.90			
50300285	FORM LINER TEXTURED SURFACE	SQ FT	21,871						21,871
50300300	PROTECTIVE COAT	SQ YD	10,877		2629.5	2629.5	2,809	2,809	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1.00		0.23	0.23	0.27	0.27	
50500505	STUD SHEAR CONNECTORS	EACH	21,456		5,256	5,256	5,472	5,472	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,076,080		271,535	271,535	266,505	266,505	
50800515	BAR SPLICERS	EACH	364		96	96	86	86	
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	17,584		3,423	3,423	5,369	5,369	
51202100	FURNISHING STEEL PILES HP14X117	FOOT	3,600		1,800	1,800			
51202305	DRIVING PILES	FOOT	21,184		5,223	5,223	5,369	5,369	
51203200	TEST PILE METAL SHELLS	EACH	10		2	2	3	3	

△ DENOTES SPECIALTY ITEM
 ** 100% STATE

FILE NAME : 0284019-INT-500.dgn
 MODEL DRIVER : Default
 PLOT DRIVER : PLOT001.PDF, Plot12.plt, etc



USER NAME : rgoertz	DESIGNED - CMS	REVISED -
PLOT SCALE : 48.0000' / in	DRAWN - TKW	REVISED -
PLOT DATE : 9/3/2013	CHECKED - CMS	REVISED -
	DATE - 07/01/2013	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 301	SECTION 3BR & 3BR-1	COUNTY WINNEBAGO	TOTAL SHEETS 290	SHEET NO. 10
CONTRACT NO. 64019				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

Rev.