PAY ITEM #	DESCRIPTION	UNIT	TOTAL	ROADWAY 0004	BRIDGE 0011	LIGHTING 0021	RETAINING WALL 0040		LIFT STATION RELOCATON 0040	
				80% FED 20% STATE	80% FED 20% STATE	VILLAGE OF HANOVER 100% LOCAL	#1	#2 AND #3	80% FED 20% STATE	VILLAGE OF HANOVER 100% LOCAL
							80% FED / 20% STATE			
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	4		4					
Z0026403	FURNISHING SOLDIER PILES (BUILT-UP SECTION)	FOOT	18				18			
Z0026404	FURNISHING SOLDIER PILES (W SECTION)	FOOT	99				99			
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	338		132		66	140		
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	35	35						
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	153	153						
Z0056900	SANITARY SEWER 8"	FOOT	455						263	192
Z0062456	TEMPORARY PAVEMENT	SQ YD	356	106					151	99
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	816		816					
Z0073100	TEMPORARY SHORING	EACH	2		2					
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1		1					
Z0075496	CONCRETE RETAINING WALL REMOVAL	FOOT	11	11						
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1500	1500						
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1						
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4						
* 67201100	SEALING ABANDONED MONITORING WELLS	EACH	8	8						

*Specialty Items

Rev. 10-29-13

Rev.

design firm no. 184001036 whks engineers + planners + land surveyors

USER NAME = gjameson	DESIGNED -	REVISED
FILE NAME = Z64E08-SHT-SUM.dgn	CHECKED -	REVISED
PLOT SCALE = 10.0000 ' / IN.	DRAWN -	REVISED
PLOT DATE = 8/6/2013	CHECKED -	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL ROUTE 84 OVER APPLE RIVER

SCALE: NTS | SHEET NO. 10 OF 10 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308	103BR-4	JO DAVIESS	159	14

CONTRACT NO. 64E08

ILLINOIS FED. AID PROJECT