

PEDESTRIAN WALKWAY SCHEDULE					
LOCATION	PIPE CULVERTS CLASS D TYPE 1, 12"	PIPE CULVERT REMOVAL	6" HMA BASE COURSE SQ. YD.	4" AGG BASE COURSE TYPE A SQ. YD.	EARTH EXCAVATION C.Y.
STA TO STA	FOOT	FOOT			
NORTHBOUND					
FROM CULVERT TO R.O.W. LINE			91.8	91.8	
STA 268+88 LT 52' TO STA 267+10 LT 52' FROM MEDIAN CENTER TO R.O.W.	22	22			52.3
NORTHBOUND SUBTOTAL	22	22	92	92	52
SOUTHBOUND					
FROM CULVERT TO R.O.W. LINE			87.1	87.1	
STA 268+89 RT 56' TO STA 267+12 RT 63' FROM MEDIAN CENTER TO R.O.W.	24	24			51.0
SOUTHBOUND SUBTOTAL	24	24	87	87	51
TOTAL	46	46	179	179	103

GUARDRAIL											
LOCATION	TERM MRK. DA	TBT TY 1 (SPECIAL) TANG	TBT TY 2	TBT TY 6	SPBGR TY A 6' POSTS (FOOT)	GUARDRAIL MARKERS, TYPE A	HMA SHOULDER 6"	BARRIER WALL MARKERS*	GR REMOVAL	LONG-SPAN GR OVER CULVERT, 18'9" **	LINEAR DELINEATOR PANELS, 6 "
	EA	EA	EA	EA	FT	EA	SO YD	EACH	FOOT	FOOT	EACH
STR. NO. 046-0003 NB											
NE QUAD			1	1	427.75	6	160		372		
NW QUAD			1	1	302.75	4	130		299		
BRIDGE NB								14			14
SE QUAD	1	1		1	469.5	8	259		718	168.75	
SW QUAD	1	1		1	50	3	81		397	168.75	
STR. NO. 046-0004 SB											
NE QUAD	1	1		1	247.25	4	109		343		
NW QUAD	1	1		1	422.25	6	189		341		
BRIDGE SBI								14			14
SE QUAD			1	1	54	3	126		322	168.75	
SW QUAD			1	1	376	7	173		272	168.75	
TOTAL	4	4	4	8	2350	41	1226	28	3064	675	28

- PLACE BARRIER WALL MARKERS ON THE PARAPET ON THE BRIDGE
- ** BEGIN STA. 266+06 TO END STA. 267+75

PAVEMENT REMOVAL & REPLACEMENT								
STA. TO STA.	LENGTH	PAVT REM	PAVED SHOULDER REMOVAL	AGG BASE CSE TYPE A 4"	HMA SHOULDER 10" (1)	HMA BASE CSE 17"	GRANULAR CULVERT BACKFILL	APPR. SLAB REMOVAL (2)
	FEET	SO YD	SO YD	SO YD	SO YD	SO YD	CU YD	SO YD
STAGE I								
266+67 NB 267+33 NB	66	176.0	117.3	293.3	117.3	176.0		178
STAGE II								
266+67 SB 267+33 SB	66	176.0	117.3	293.3	117.3	176.0		178
PEDESTRIAN CULVERT								
266+67 267+33							1308.0	
GRAND TOTALS	132	352	235	587	235	352	1308	356

- (1) SEE GUARDRAIL SCHEDULE FOR HMA SHOULDER 6", FOR STABILIZATION.
- (2) STAGE 1 REMOVAL FROM STA. 256+16.13 TO 256+36.13, AND STA. 265+00.71 TO 265+20.71
STAGE 2 REMOVAL FROM STA. 256+59.29 TO 256+79.29, AND STA. 265+43.87 TO 265+63.87